FEES:
Application $150.00 Public Notice: 75.00 per submission
Abutters @_____X $7.00 each=____ Other_____

Total Received: $____Cash___ Check#_____
Date Received_____

SECTION 9.6 APPLICATION FOR SPECIAL PERMIT FOR CONSTRUCTION IN WETLAND BUFFER

TOWN OF BARRINGTON
PO Box 660; 333 Calef Highway
Barrington, New Hampshire 03825

A SPECIAL USE PERMIT allows the Town of Barrington to consider special uses which may be essential or desirable to a particular community, but which are not allowed as a matter of right within a wetlands buffer in the Wetlands Protection District Overlay, but rather only by a special use permit. A public hearing is required.

Is the proposed use permitted by right in the appropriate base zoning district? (See Table 1, Table of Uses, located in the town zoning ordinance)

-If yes, then proceed with the below criteria for a Special Use Permit pursuant to Section 9.6.
-If, on the other hand, the proposed use requires a conditional use permit, a special exception, or a variance, you must obtain that permit or approval before seeking a Special Use Permit pursuant to Section 9.6.

This application applies only to uses proposed in the Wetlands Protection District Overlay that violate the required wetland buffer. There is a separate application for a Conditional Use Permit pursuant to Section 3.4, which is also available in the town Land Use Office.

Is the proposed use related to a Site Plan or Subdivision Application? Yes X No___
Name of Project Proposed 2 Lot Subdivision
Address of Property 228 Merry Hill Rd, Barrington, NH

Tax Map 257 Lot 23&23-1 Zoning District(s) Gen. Res. Overlay _____ Total Area of Site 46.33 Ac.
Name of Applicant/Agent Christopher R. Berry, Berry's Surveying & Engineering
Mailing Address of Applicant/Agent 335 Second Crown Point Rd. Barrington, NH 03825

Telephone: 332-2863 Email: CRBerry@metrocast.net Fax:
Name of Property Owner John R. & Pamela P. Bingham
Mailing Address of Property Owner PO Box 738, Barrington, NH 03825

Telephone: 603-973-9798 Email: Fax:

Letter of Authorization Provided___

Signature of Owner JB
Deed Provided___

Revised 5/22/13

LAND USE OFFICE
MAR 15 2016
RECEIVED

Describe in detail all existing uses and structures on the subject property (You may attach a separate typed sheet):

Size of Impact

Describe in detail all proposed uses, structures, construction, or modifications requiring a Special Use Permit.

Describe in detail how the following standards of the Town of Barrington Zoning Ordinance under Section 9.6 "Special Permit for Construction in a Wetlands Buffer" have been satisfied by your proposal. (You may attach a separate sheet.)

1. The proposed use is in keeping with the intent and purposes set forth in the zoning ordinance as permitted in the base zoning district (See Table 1, Table of Uses, located in the zoning ordinance). If the base zoning district requires a conditional use permit or special exception for the proposed use, one must already have been obtained; or if the proposed use is not listed on the Table of Uses or is listed but not permitted, one must already have obtained a variance.

2. After a review of all reasonable alternatives, it is determined to be infeasible to place the proposed structure or use outside of the buffer zone.

3. The proposed structure or use must be set back as far as possible from the delineated edge of the wetland or surface water.

4. Appropriate erosion control measures must be in place prior to and during construction.

5. Any disturbance to the surrounding buffer zone must be repaired and restored upon completion of construction.

LAND USE OFFICE
MAR 15 2016
RECEIVED

6. All available mitigation measures to address changes in water quality and quantity be implemented, along with design and construction methods to minimize adverse impacts, if required by the Planning Board.

Statement of Assurance and Agreement:

I hereby certify that to the best of my knowledge this submitted application information is true and correct. All proposed development will be in conformance with the information contained on the application and in the approved plan as well as the provisions of the Town of Barrington ordinances and regulations.

The Owner/Agent, by filing an application, hereby grants permission for members of the Board and staff to enter onto the subject property for the purposes of this review.

Applicant/Agent Signature — Date 3-15-16

Owner Signature SB — Date

Owner Signature — Date 3-15-16.

Staff Signature — Date

LAND USE OFFICE
MAR 15 2016
RECEIVED



MERRY HILL ROAD

PLAN FOR THE 9.6 APPLICATION
FOR
JACK BINGHAM
MERRY HILL ROAD
TAX MAP 257, LOT 23 & 23-1

LAND USE OFFICE
MAR 15 2016
RECEIVED

BERRY SURVEYING & ENGINEERING
335 SECOND CROWN POINT RD.
BARRINGTON, N.H. 332-2863

SCALE : 1 IN. EQUALS 80 FT.

DATE : MARCH 15, 2016

FILE NO. : DB 2015 - 129

E1



SILT FENCE CONSTRUCTION SPECIFICATIONS

1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8" THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A
2. MAXIMUM 10' APART, AND DRIVEN A MINIMUM OF 16" INTO THE GROUND WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER,
3. THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY-PASSING MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT
4. REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE
5. FOR SEDIMENT STORAGE SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND
6. THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER. THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED

SILT FENCE MAINTENANCE

1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE IMMEDIATELY IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME
2. INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY. SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY STORM EVENT.
3. THE DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE
4. FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

SILT FENCE DETAIL
N.T.S.

E2



SILT FENCE/HAYBALE BARRIER DETAIL
THIS METHOD TO BE USED ALONG THE REAR OF THE PROPERTY

E3



SILT SOXX/SILT FENCE DETAIL
NOT TO SCALE

E4



STAKED HAYBALE DETAIL
NOT TO SCALE

HAY BALE CHECK DAM DETAIL
(NOT TO SCALE)

E5

STABILIZED CONSTRUCTION ENTRANCE



1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 1 TO 2 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.
2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET, EXCEPT FOR A SINGLE RESIDENTIAL LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.
3. THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES.
4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS OR 10 FEET, WHICH EVER IS GREATER.
5. GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE. FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT.
6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE, IF PIPING IS IMPRACTICAL, A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.
7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY.

E6

EROSION CONTROL MIX BERM



EROSION CONTROL MIX BERMS SHALL BE USED ONLY AS FOLLOWS:
(A) BERMS SHALL BE USED IN AREAS WHERE EROSION WILL OCCUR ONLY IN THE FORM OF SHEET EROSION AND THERE IS NO CONCENTRATION OF WATER IN A CHANNEL OR DRAINAGE WAY ABOVE THE BERM.
(B) THE BERMS SHALL BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSELY AS PUSSIBLE.
(C) THE BERMS SHALL BE INSTALLED ON SLOPES LESS THAN 5%.
(D) SUBJECT TO (E) BELOW, THE MIX SHALL HAVE AN ORGANIC PORTION BETWEEN 80 AND 100% DRY WEIGHT BASIS, AND BE FIBROUS AND ELONGATED SUCH AS FINE SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR EQUIVALENT MANUFACTURED WOOD PRODUCTS.
(E) WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS SHALL NOT BE USED AS ORGANIC MATERIAL.
(F) THE MIX SHALL NOT CONTAIN SILTS, CLAY, OR FINE SANDS.
(G) THE MIX SHALL HAVE A PARTICLE SIZE BY WEIGHT OF 70 TO 85% PASSING A 6-INCH SCREEN AND A MAXIMUM OF 85% PASSING THE 0.05" NON SIEVE.
(H) THE MIX PH SHALL BE BETWEEN 5.0 AND 8.0
(I) THE BERM SHALL BE AT LEAST 12 INCHES HIGH AND AT LEAST 2 FEET WIDE.

E7

LINED DRIP EDGE



E8 TEMPORARY EROSION CONTROL MEASURES

1. THE SMALLEST PRACTICAL AREA OF LAND SHALL BE EXPOSED AT ANY ONE TIME
2. EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED, DIRECTED BY THE ENGINEER
3. ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN ONE POUND OF SEED PER 50 SQUARE YARDS OF AREA. (SEE SEED SPECIFICATIONS E102)

   3a. ALL DISTURBED AREAS WILL BE RESTABILIZED WITHIN 60 DAYS. AT ANY ONE TIME, NO MORE THAN 5 ACRES, (217,800 Sq. Ft.) WILL BE DISTURBED.
4. SILT FENCES AND STRAW OR HAY BALES BARRIERS SHALL BE INSPECTED PERIODICALLY AND AFTER EVERY RAIN DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED OF.
5. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VEGETATED
6. PER THE EPA REQUIREMENTS THERE WILL BE A LOG OF THE EROSION CONTROL INSPECTIONS EVERY 7-14 DAYS PLEASE FIND SWPPP PREPARED BY BS&E (AFTER LOCAL APPROVAL)
7. DITCHES, SWALES, AND BASINS SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
8. ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER 0.5" OR GREATER RAIN EVENT

E9

WINTER STABILIZATION NOTES

1. All disturbed areas that do not have at least 85% vegetative coverage prior to October 15th, shall be stabilized by applying mulch at a rate of 3-4 tons per acre. All side slopes, steeper than 4:1, that are not directed to swales or detention basins, shall be lined with biodegradable/photodegradable "jute matting" (Excelsior's Curlex II or equal). All other slopes shall be mulched and tacked at a rate of 3-4 tons per acre. The application of mulch and/or jute matting shall not occur over existing snow cover. If the site is active after November 15th, any snow that accumulates on disturbed areas shall be removed. Prior to spring thaw all areas will be stabilized, as directed above.

2. All swales that do not have fully established vegetation shall be either lined with temporary jute matting or temporary stone check dams (appropriately spaced). Stone check dams will be maintained throughout the winter months. If the swales are to be matted with permanent liners or riprap with engineering fabric, this shall be completed prior to winter shutdown or as soon as they are properly graded and shaped.

3. Prior to Nov. 15th all roadway and parking areas shall be brought up to and through the bank run gravel application. If these areas' elevations are proposed to remain below the proposed subgrade elevation, the subgrade material shall be roughly crowned and a 3" layer of crushed gravel shall be placed and compacted. This will allow the subgrade to shed runoff and will reduce roadway erosion. This crushed gravel does not have to conform to NH DOT 304.3, but shall have between 15-25% passing the #200 sieve and the largest stone size shall be 2". If the site is active after November 15th, any accumulated snow shall be removed from all roadway and parking areas.

4. After October 15th, the end of New Hampshire's average growing season, no additional loam shall be spread on side slopes and swales. The stockpiles that will be left undisturbed until spring shall be seeded by this date. After October 15th, any new or disturbed piles shall be mulched at a rate of 3-4 tons per acre. All stockpiles that will remain throughout the winter shall be surrounded with silt fencing.

E10



NOTES
1. ALL MATERIAL TO MEET FILTREXX SPECIFICATIONS.
2. TOP MEDIA FILL TO MEET APPLICATION REQUIREMENTS.
3. COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.
4. SILTSOXX MAY BE USED IN PLACE OF SILT FENCE OR OTHER SEDIMENT BARRIERS.
5. SILTSOXX COMPOST/SOIL/ROCK/SEED FILL MATERIAL SHALL BE ADJUSTED AS NECESSARY TO MEET THE REQUIREMENTS OF THE SPECIFIC APPLICATION.
6. FILTREXX SOXX IS A REGISTERED TRADEMARK OF FILTREXX INTERNATIONAL, LLC.

Filtrexx International, LLC
29451 Grafton Eastern Rd | Grafton, OH 44044
440-926-2107 | fax: 440-926-4021
www.filtrexx.com

FILTREXX SEDIMENT CONTROL
NOT TO SCALE



E11

LAND USE OFFICE
MAR 15 2016
RECEIVED

E-101

REVISION	DATE	DESCRIPTION

9.6 BUFFER PLAN
FOR
JACK BINGHAM
MERRY HILL ROAD
BARRINGTON, N.H.
TAX MAP 257, LOT 23 & 23-1

BERRY SURVEYING & ENGINEERING
335 SECOND CROWN POINT ROAD
BARRINGTON, NH 03825 (332-2863)

SCALE : AS MARKED
DATE : MARCH 15, 2016
FILE NO. : DB 2015-129

STATE OF NEW HAMPSHIRE
KENNETH A. BERRY
No. 14243
LICENSED PROFESSIONAL ENGINEER

E12

E13

E14

E17

NOTE: THIS PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.

NOTE: Temporary seed mix for stabilization of turf shall be winter rye or oats at a rate of 2.5 lbs. per 1000 s.f. and shall be placed prior to OCT. 15, if permanent seeding not yet complete.

SEEDING GUIDE

USE	SEEDING MIXTURE (1)	DROUGHTY	WELL DRAINED	MODERATELY WELL DRAINED	POORLY DRAINED
STEEP CUTS AND FILLS, EMBANKMENTS AND DISPOSAL AREAS	A	FAIR	GOOD	GOOD	FAIR
	B	FAIR	GOOD	FAIR	FAIR
	C	GOOD	GOOD	EXCELLENT	POOR
	D	FAIR	FAIR	GOOD	EXCELLENT
		FAIR	EXCELLENT	EXCELLENT	POOR
WATERWAYS, EMBANKMENT SPILLWAYS, AND OTHER CHANNELS WITH FLOWING WATER	A	GOOD	GOOD	GOOD	FAIR
	B	GOOD	EXCELLENT	EXCELLENT	FAIR
	C	GOOD	EXCELLENT	EXCELLENT	FAIR
LIGHTLY USED PARKING LOTS, LOW AREAS, MULCHED LANES, AND LOW INTENSITY USE RECREATION SITES	A	GOOD	GOOD	GOOD	FAIR
	B	GOOD	GOOD	FAIR	POOR
	C	GOOD	EXCELLENT	EXCELLENT	FAIR
	D	FAIR	GOOD	GOOD	EXCELLENT
PLAY AREAS AND ATHLETIC FIELDS, PICNIC AREAS AND FOR CODE B-4-1	E	FAIR	EXCELLENT	EXCELLENT	POOR
	G	FAIR	EXCELLENT	EXCELLENT	POOR

GRAVEL PIT SEE MIXTURE 24 IN APPENDIX FOR RECOMMENDATION REGARDING RECLAMATION OF SAND AND GRAVEL PITS

* REFER TO SEEDING MIXTURES AND RATES IN TABLE 3-1(a). PROPER DRAINED SOILS ARE NOT LIKELY FOR THESE PLAYING AREAS AND ATHLETIC FIELDS

RECOMMENDED

SEEDING RATES

MIXTURE:	POUNDS PER ACRE	POUNDS PER 1,000 Sq. Ft.
A. TALL FESCUE	20	0.45
CREEPING RED FESCUE	20	0.45
RED TOP	2	0.05
TOTAL	42	0.95
B. TALL FESCUE	15	0.35
CREEPING RED FESCUE	10	0.25
CROWN VETCH	15	0.35
OR		
FLAT PEA	20	0.75
TOTAL	40 OR 35	0.95 OR 1.35
C. TALL FESCUE	24	0.55
CREEPING RED FESCUE	24	0.55
BIRDS FOOT TREFOIL	REMOVED	REMOVED
TOTAL	48	1.10
D. TALL FESCUE	20	0.45
FLAT PEA	30	0.75
TOTAL	50	1.20
E. CREEPING RED FESCUE 1/	50	1.15
KENTUCKY BLUEGRASS 1/	50	1.15
TOTAL	100	2.30
F. TALL FESCUE 1	150	3.60

SEEDING SPECIFICATIONS

1. Grading and Shaping
   a. Slopes shall not be steeper than 2:1;3:1 slopes or flatter are preferred. Where mowing will be done, 3:1 slopes or flatter are recommended.
2. Seedbed Preparation
   a. Surface and seepage water should be drained or diverted from the site to prevent drowning or winter killing of the plants.
   b. Stones larger than 4 inches and trash should be removed because they interfere with seeding and future maintenance of the area. Where feasible, the soil should be tilled to a depth of about 4 inches to prepare a seedbed and mix fertilizer and lime into the soil. The seedbed should be left in reasonably firm and smooth condition. The last tillage operation should be performed across the slope wherever practical.
3. Establishing a Stand
   a. Lime and fertilizer should be applied prior to or at the time of seeding and incorporated into the soil kinds and amounts of lime and fertilizer should be based on an evaluation of soil tests. When a soil test is not available, the following minimum amounts should be applied:
   Agricultural limestone, 2 tons per acre or 100lbs. per 1,000 sq.ft.
   Nitrogen(N), 50lbs. per acre or 1.1lbs. per 1,000 sq.ft.
   Phosphate(P205), 100lbs. per acre or 2.2lbs. per 1,000 sq.ft.
   Potash(K20), 100lbs. per acre or 2.2lbs. per 1,000 sq.ft.
   (Note: This is the equivalent of 500lbs. per acre of 10-20-20 fertilizer or 1,000lbs. per acre of 5-10-10.)
   b. Seed should be spread uniformly by the method most appropriate for the site. Methods include broadcasting, drilling and hydroseeding. Where broadcasting is used, cover seed with .25 inch of soil or less, by cultipacking or raking.
   C. Refer to Table(G-E1 this sheet) for appropriate seed mixtures and Table(H-E1 this sheet) for rates of seeding. All legumes (crownvetch, birdsfoot trefoil, and flatpea) must be inoculated with their specific inoculant.
   d. When seeded areas are mulched, plantings may be made from early spring to early October. When seeded areas are not mulched, plantings should be made from early spring to May 20 or from August 10 to September 1.
4. Mulch
   a. Hay, straw, or other mulch, when needed, should be applied immediately after seeding.
   b. Mulch will be held in place using appropriate techniques from the Best Management Practice for mulching. Hay or straw mulch shall be placed at a rate of 90lbs per 1000 s.f.
5. Maintenance to Establish a Stand
   a. Planted area should be protected from damage by fire, grazing, traffic, and dense weed growth.
   b. Fertilization needs should be determined by onsite inspections. Supplemental fertilizer is usually the key to fully complete the establishment of the stand because most perennial stake 2 to 3 years to become established.
   c. In waterways, channels, or swales where uniform flow conditions are anticipated, occasional mowing may be necessary to control growth of woody vegetation.

DEFINITION OF STABLE:

1. WHEN A BASE COURSE GRAVEL HAS BEEN INSTALLED IN AN AREA TO BE PAVED
2. WHEN A MINIMUM OF 85% VEGITATIVE GROWTH OCCURS
3. WHEN A MINIMUM OF 3" OF NON-EROSIVE MATERIAL, SUCH AS STONE OR RIP-RAP HAS BEEN INSTALLED.
4. WHEN PROPER EROSION CONTROL BLANKETS, SUCH AS CURLEX II, C350 OR OTHER DOT APPROVED MATTING, HAS BEEN INSTALLED PROPERLY.
5. HAY MULCH OR OTHER APPROVED METHODS SHALL BE USED TO CONTROL EROSION OF NEWLY GRADED AREAS. ALL CUT AND FILL SLOPES SHALL BE SEEDED AND MULCHED WITHIN 72 HOURS AFTER THEIR CONSTRUCTION.

E15



TOPSOIL STOCKPILE MOUND

NOT TO SCALE

E16

E18



GRASS TREATMENT SWALE

NOT TO SCALE

INSPECT ANNUALLY FOR EROSION, SEDIMENT ACCUMULATIONS, VEGETATION LOSS, & INVASIVE SPECIES. REPAIR AS NECESSARY.

MOW GRASS ANNUALLY TO A DEPTH OF 4"

E19



SLOPE STABILIZATION DETAIL

NOT TO SCALE

E20



NOTE : STAKING PATTERNS SHALL FOLLOW MANUFACTURERS RECOMMENDATIONS. MINIMUM SPACING 3' - 0" O.C. ACROSS FABRIC.

INSTALLATION OF EROSION CONTROL FABRICS

NOT TO SCALE

E21

LAND USE OFFICE
MAR 15 2016
RECEIVED

E-102

REVISION	DATE	DESCRIPTION

9.6 BUFFER PLAN
FOR
JACK BINGHAM
MERRY HILL ROAD
BARRINGTON, N.H.
TAX MAP 257, LOT 23 & 23-1

BERRY SURVEYING & ENGINEERING
335 SECOND CROWN POINT ROAD
BARRINGTON, NH 03825 (332-2863)

SCALE : AS MARKED
DATE : MARCH 15, 2016
FILE NO. : DB 2015-129

STATE OF NEW HAMPSHIRE
KENNETH A. BERRY
No. 14243
LICENSED PROFESSIONAL ENGINEER