

SCALE: 1" = 2.000'

## THE HOMESTEAD SUBDIVISION - PHASE II

**FOR** 

**GERRIOR LANE TRUST** 1550 FALMOUTH ROAD, SUITE 15 CENTERVILLE, MA 02632

MAY 15, 2013

## **OWNER**

**GERRIOR LANE TRUST** 1550 FALMOUTH ROAD, SUITE 15 CENTERVILLE, MA 02632

## **ENGINEER**



## SURVEYOR




## WETLAND SCIENTIST

WEST ENVIRONMENTAL, INC. 122 MAST ROAD, SUITE 6 LEE, NH 03824 (603) 659-0416 CONTACT: MARK WEST

## SOIL SCIENTIST

JOSEPH W. NOEL P.O. BOX 174 S. BERWICK, ME (207) 384-5587



SCALE: NTS


LAND USE OFFICE

MAY 15 2013


RECEIVED


## TABLE OF CONTENTS


TITLE	SHEET
SURVEYOR PLANS	
SUBDIVISION PLAN	.1 OF 2
SUBDIVISION PLAN	2 OF 2
SITE SPECIFIC SOILS MAP	.C1
SUBDIVISION SITE PLAN	. <b>C2</b>
ROADWAY PLAN AND PROFILE (HERITAGE LANE)	C3
ROADWAY PLAN AND PROFILE (SHARED DRIVEWAY)	.C4
ROADWAY PLAN AND PROFILE (ST. MATTHEWS DRIVE)	C5
ROADWAY CROSS SECTIONS (HERITAGE LANE)	XS1 - XS3
ROADWAY CROSS SECTIONS (SHARED DRIVEWAY)	XS4 - XS5
ROADWAY CROSS SECTIONS (ST. MATTHEWS DRIVE)	XS6 - XS7
DETAILS	. D1 - D4





NO.	revisions	DATE	
Q.	INITIAL SUBMISSION TO BARRINGTON PLANNING BOARD	5/15/13	W









































MAY. 15 2013

RECEIVED

LEGEND: 340.18 PROPOSED ELEVATION 360.0 EXISTING ELEVATION

PROPOSED GRADE ---- EXISTING GRADE

NOTE: REFER TO SHARED DRIVE CROSS SECTION FOR ADDITIONAL INFORMATION

JOB: 11-060

a Ö

SHARED DRIVE CROSS SECTIONS prepared for GERRIOR LANE TRUST IE HOMESTEAD SUBDIVISION PHASE II

ENGINEERING, PC

SRAIDOU ST., P.O. BOX 39


SRAIDOU ST., P.O. BOX 39


SRAIDOU ST., P.O. BOX 39


FROM: (CAN) SGS44277 FAX (CAN) 565-4627


FROM: (CAN) 565-4777 FAX (CAN) 565-4777

FROM: (CAN) 565-4777 FAX









LAND USE OFFICE

MAY 15 2013

RECEIVED

340.18 PROPOSED ELEVATION 360.0 EXISTING ELEVATION PROPOSED GRADE ---- EXISTING GRADE

R.O.W. RIGHT OF WAY

NOTE: REFER TO ST, MATTHEWS DRIVE CROSS SECTION FOR ADDITIONAL INFORMATION

ST. MATTHEWS DRIVE CROSS SECTIONS prepared for GERRIOR LANE TRUST E HOMESTEAD SUBDIVISION PHASE II ENGINEERING, PC

S PAUDO ST. PLO SE ST. PLO JOB: 11−060

## **CONSTRUCTION SEQUENCING AND EROSION CONTROL NOTES**

POSTING CONDITIONS

1. THE PROJECT LOCATION IS: LATITUDE 43"-10"-17", LONGITUDE 71"-04"-39".

2. THE TOTAL PARCEL CONSISTS OF "APPROXIMATELY 125 ACRES STRADDLING THE NOTTINGHAM/BARRINGTON TOWN LINE WITH ACCESS FROM ROUTE 4. THE PARCEL IS CURRENLTY SUBDIVIDED INTO 37 RESIDENTIAL LOTS, APPROVED IN 2005. 12 OF THE 37 LOTS ARE LOCATED IN NOTTINGHAM.

3. THE ORIGINAL PROJECT WAS PROPOSED TO BE CONSTRUCTED IN TWO PHASES, PHASE 1 HAS BEEN COMPLETED. ALL BUT ONE LOT IN PHASE 1 HAS BEEN DEVELOPED.

PROPOSED PROJECT

1. THIS PROJECT IS THE RE-SUBDIMISION OF THE PHASE 2 PORTION OF THE ORIGINAL DEVELOPMENT INTO A TOTAL OF 10 LOTS AND 1,000 FT OF NEW ROAD. TWO OF THE PROPOSED LOTS WILL HAVE FRONTAGE ON ST. MATHEMS DRIVE AND BE ACCESSED BY A SHARED DRIVEWAY.

2. THE BALANCE OF THE PHASE 2 LAND AREA WILL REMAIN UNDEVELOPED AND BE ADDED TO THE EXISTING CONSERVATION LAND CREATED UNDER THE ORIGINAL SUBDIVISION.

3. THE TOTAL AREA OF DISTURBANCE FOR BOTH PHASES IS 267,271 SF.

AREA OF DISTURBANCE/STABLIPATION

A. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SMALL THE AREA OF UNSTABILIZED SOIL EXCEED 5 ACRES AT ANY ONE TIME BEFORE THE AREA IS STABILIZED.

A.M. AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED:

1. IN AREAS TO BE PAYED, BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHOOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION, ITEM NO. 304.1 OR 304.2 HAVE BEEN INSTALLED.

C. ALL DISTURBED AREAS SHALL BE TEMPORARILY STABILIZED WITHIN 45 DAYS AND PERMANENTLY SHALL BEEN ASSAND.

## EROSION CONTROL PRACTICES:

A. INSTALLATION: ALL EROSION CONTROLS AS SHOWN ON THE GRADING PLAN, TYPICAL DETAILS, AND IN CONFORMANCE WITH THE EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE. MANUFACTURER'S SPECIFICATIONS SHALL BE FOLLOWED.

B. INSPECTION OF THE REGION CONTROLS WEEKLY AND AFTER EVERY RAIN EVENT OF 1. INCREDED THE REGION CONTROLS WEEKLY AND AFTER EVERY RAIN EVENT OF 2. TEMPORARY STABILIZATION PRACTICES SHALL BE INSPECTED ONCE PER WEEK DURING CONSTRUCTION UNTIL EXPOSED SURFACES ARE STABILIZED.

3. ANY SIGNS OF RILL OR GULLY EROSION SHALL BE IMMEDIATELY REPAIRED.

C. MAINTENANCE:

1. MAINTAIN EROSION CONTROLS PER THE TYPICAL DETAILS AND IN CONFORMANCE WITH THE EROSION AND SEDIMENT CONTROL NOTES ON THIS PAGE.

ALVAL
ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE 85%
VEGETATIVE COVER HAS BEEN ESTABLISHED.
AFTER REMOVAL, ALL DISTURBED AREAS SHALL BE REGRADED, FERTILIZED, AND
RESEEDED. MONITOR TO ENSURE VEGETATIVE GROWTH IS ESTABLISHED AND
REPAIR AS HEEDED UNIL MINIMUM OF 65% VEGETATIVE COVER IS ESTABLISHED.

RESPARE AS NECCED LYNTI. MINIMUM OF 55% VEGETATIVE COVER IS ESTABLISHED.

COLD WTANTER SITE STABLEZATION

A. SHALL BE LYTHIZED BETWEEN NOVEMBER 30TH AND MAY 1ST. THE AREA OF EXPOSED, UNSTABILIZED SOIL SHALL BE LUMITED TO I ACRE AND SHALL BE PROTECTED AGAINST EROSION BY THE FOLLOWING METHODS PRIOR TO ANY THAW OR SPRING MELT EVENT.

B. ALL PROPOSED VEGETATED AREAS HAVING A SLOPE OF LESS THAN 15% WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY MOVEMBER 30TH, OR WHICH AND SOIL OF THE STABLE STA

SPECIFIED IN (9)(1-5);
INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX, MEETING THE INSTALLATION OF ANCHORED HAY MULCH OR EROSION CONTROL MIX, MEETING THE CRITERIA SPECIFICD IN (8)(1-5) SHALL NOT OCCUR OVER SNOW OF GREATER THAN INCH IN DEPTH OR ON PROZEN GROUND.

ALL PROPOSED COLD WEATHER STABLIZATION IN ACCORDANCE WITH (A) OR (8) SHALL BE COMPLETED WITHIN A DAY OF ESTABLISHING THE GRADE THAT IS FINAL OR THAT OTHERWISE WILL EXIST FOR MORE THAN 5 DAYS.

ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85X VEGETATIVE GROWTH BY NOVEMBER 30TH, OR WHICH ARE DISTURBED AFTER NOVEMBER 30TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BILANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.

FOR THE DESIGN FLOW CONDITIONS.

FOR THE DESIGN FLOW CONDITIONS.

CONSTRUCTION OF THE ROAD OR PARKING SURFACES WHERE ACTIVE CONSTRUCTION OF THE ROAD OR PARKING SURFACES WHERE ACTIVE CONSTRUCTION OF THE ROAD OR PARKING AREA HAS STOPPED FOR THE WINTER SEASON SHALL BE PROTECTED WITH A MINIMUM 3-INCH LAYER OF BASE COURSE GRAVELS MEETING THE GRADATION REQUIREMENTS OF NHOOT STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION, ITEM NO. 304.1 OR 304.2.

## TEMPORARY VEGETATION

A. STE PREPARTION

1. INSTALL EROSION ANS SEDIMENT CONTROL MEASURES AS SPECIFIED ABOVE.

2. ENSURE RUNDFF IS DIMENTED FROM SEEDED AREA.

3. ON SLOPES OF 4:1 OR SIEEPER, CREATE HORIZONTAL GROOMES PERPENDICULAR TO THE DIMECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNDFF.

B. SEED BED PREPARATION

1. REMOVE STONES AND TRASH FROM AREA TO BE SEEDED,

2. COMPACTED SOIL SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME, AND SEED,

3. APPLY FERTILIZER AT A RATE OF 600 LBS PER AGRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT

C. SEFENIKATE OF 3 TONS PER AGRE.

C. SEEDING

1. SEED PER THE FOLLOWING RECOMMENDATIONS

SEASON	APPLICATION DATE	MIXTURE TYPE	QUANTITY (lb./Ac.)
EARLY SPRING	NO LATER THAN 5/15	OATS	80
LATE SPRING/ FALL	4/1 TO 6/1 & 8/15 TO 9/15	PERENNIAL RYE	30
EARLY SPRING/ FALL	4/1 TO 5/15 & 8/15 TO 9/15	ANNUAL RYE	40
FALL	8/15 TO 9/15	WINTER RYE	112

APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLUBRY INCLUDING SEED AND FERTILIZER), NORMAL SEEDING DEPTH IS FROM ¼ TO ½, INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LET ON SOIL SURFACE, SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING.

WHEN HYDROSEEDING.

3. TEMPORARY SEEDING SHOULD TYPICALLY OCCUR PRIOR TO SEPTEMBER 15TH.

AREAS SEEDED BETWEEN MAY 15TH AND AUGUST 15TH SHOULD BE COVERED WITH HAY OR STRAW MUICH.
VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA SHOULD BE ACHIEVED PRIOR TO OCTOBER 15TH. IF THIS CONDITION IS NOT ACHIEVED, IMPLEMENT OTHER TEMPORARY STABILIZATION MEASURES FOR

OVERWINTER PROTECTION.

INTERNANCE
TEMPORARY SEEDING SHOULD BE INSPECTED WEEKLY AND AFTER ANY RAINFALL
EXCEDING SY INCH IN 24 HOURS ON ACTIVE CONSTRUCTION SITES. TEMPORARY
SEEDING SHOULD ALSO BE INSPECTED JUST PRIOR TO SEPTEMBER 15, TO
ASCERTAIN WHETHER ADDITIONAL SEEDING IS REQUIRED TO PROVIDE
STABILIZATION OVER THE WINTER PERIOD.
BASED ON INSPECTION, AREAS SHOULD
SASED ON INSPECTION, AREAS SHOULD
STABILIZATION OF EXPOSED SOILS. IF IT IS TOO LATE IN THE PLANTING SEASON
TO APPLY ADDITIONAL SEED, THEN OTHER TEMPORARY STABILIZATION MEASURES
SHOULD BE IMPLEMENTED.
AT A MINIMUM, B5X OF THE SOIL SURFACE SHOULD BE COVERED BY
VEGETATION.
IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS
SHOULD BE MADE AND AREAS SHOULD BE RESECDED, WITH OTHER TEMPORARY
MEASURES (E.G., MULCH) USED TO PROVIDE EROSION PROTECTION DURING THE
PERIOD OF VEGETATION ESTABLISHMENT.

REMAINENT MODITATION

1. REFER TO SITE PREPARATION

1. REFER TO SITE PREPARATION

1. REFER TO SITE PREPARATION

1. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNITL A REASONABLY UNIFORM, FINE SEEDBED IS PREPARED. ALL BUT CLAY OR SILTY SOILS AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE.

2. REMOVE FROM THE SURFACE ALL STONES 2 INCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, CONCRETE, CLODS, LUMPS, TRASH OR OTHER UNSUITABLE MATERIAL.

3. INSPECT SEEDBED JUST BEFORE SEEDING, IF TRAFFIC HAS LEFT THE SOIL COMPACTED; THE AREA MUST BE TILLED AND FIRMED AS ABOVE.

4. WHERE THE SOIL HAS SEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED.

5. APPLY FERTILIZER AT A RATE OF BOOL BS PER ACRE OF 10—10—10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE.

A MAIE OF 3 TONS PER AURE.

SEEDING

1. GRASS SEED MIXTURE 'C' SHALL BE APPLIED AT THE SPECIFIED RATE
AS NOTED IN THE 'SEED MIXTURES FOR PERMAMENT VEGETATION' TABLE.

2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE
SEEDER ON HYDROSEEDER (SLURRY INCLUDING SEED AND, FERTILIZER), NORMAL
SEEDING DEPTH IS FROM X TO X, INCH. HYDROSEEDING THAT INCLUDES MULCH
MAY BE LEFT ON SOIL SURFACE. SEEDING OPERATIONS SHOULD BE ON THE

SEEDING DEPIN IS FROM & IN INCH. HYDROSEDING INAI INCLUDES MULCH MEAN COME.

AND COME.

WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR OPERATIONS WITH A ROLLER, OR LIGHT DRAG.

OPERATIONS WITH A ROLLER, OR LIGHT DRAG.

WHEN HYDROSEEDING (MYDRAULIC APPLICATION), PREPARE THE SEEDISED AS SPECIFIED ABOVE OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND TO REMOVE SUFFACE STOKES LARGER THAN 2 INCHES IN DUMTER.

SLOPES MUST BE NO STEEPER THAN 2 TO 1.

LIME AND FERTILIZER MY BE APPLIED SMULTANEOUSLY WITH THE SEED. THE USE OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). BETTER PROTECTION IS GANED BY USING SACRED BY USING SEEDING RATER MULCH.

WITH ADDRESS MUST BE INCREASED 10% WHEN HYDROSEEDING.

NITEMANCE PERMANCENTLY SEEDED AREAS SHOULD BE INSPECTED MONTHLY.

NTENANCE
PERMANENTLY SEEDED AREAS SHOULD BE INSPECTED MONTHLY.
MOW SEEDED AREAS AS NECESSARY.
BASED ON INSPECTION, AREAS SHOULD BE REPAIRED AND/OR RESEEDED TO
ENSURE BS% OF THE SOIL SURFACE IS COVERED BY YEGETATION.

## MULCHING & FROSON CONTROL MATTING

EERAL APPLY PRIOR TO A STORM EVENT. CLOSELY MONITOR THE WEATHER TO HAVE ADEQUATE WARNING OF SIGNIFICANT STORMS.
MULCHING WITHIN A SPECIFIED TIME PERIOD FROM ORIGINAL SOIL EXPOSURE A WITHIN 100 FEET OF WETLANDS THE TIME PERIOD SHOULD BE NO GREATER THAN 7 DAYS.

B. ON THE REAS IT SHALL BE NO GREATER THAN 14 DAYS.

THAN 1 DAYS.

B. HOTHER AREAS IT SHALL BE NO GREATER THAN 14 DAYS.

B. TEMPORARY MULCHING

1. HAY OR STRAW MULCHES

A. ORGANIC MULCHES INCUDING HAY AND STRAW SHALL BE AIR-DRIED, FREE OF UNDESIRABLE SEEDS AND COARSE MATERIALS.

B. APPLICATION RATE SHALL BE 2 BALES/1,000 SF (70-90 POUNDS) OR 1.5-2.0 TORS/ACRE TO COVER 75-90% OF THE GROUND.

C. ANCHORING

1. NETTING: NETTING SHALL BE JUTE, WOOD FIBER, OR BIODEGRADABLE PLASTIC NETTING INSTALLED PER MANUFACTURER'S SPECIFICATIONS.

2. TACKIFIER: APPLY POLYMER OR ORGANIC TACKIFIER TO ANCHOR HAY OR STRAW MULCH. APPLY PER MANUFACTURER'S SPECIFICATIONS.

TYPICAL APPLICATION ARTES ARE 40-60 LBS/ACRE FOR POLYMER MATERIAL AND 80-120 LBS/ACRE FOR ORGANIC LUQUID.

D. WINTER APPLICATION ARTES ARE 40-60 LBS/ACRE FOR POLYMER MADERIAL AND 80-120 LBS/ACRE FOR FOR AND MULCHED IN THE SPRING.

E. MAINTENANCE.

E. MAINTENANCE.

E. MAINTENANCE.

2. EROSION CONTROL BERNOWED AND THE AREA SEEDED AND MULCH MELL NEED TO BE REMOVED AND THE AREA SEEDED AND MULCH REPROPERTIES.

B. APPLICATION AND THING SEEDING SEEDES AND MULCH MELL AND FOR THE AREA SEEDED AND MULCH REPROPERTIES.

E. MAINTENANCE.

E. MAINTENANCE.

2. EROSION CONTROL BLANKET OR MATTING. COVER IS ESTABLISHED.

A. REFER TO PLANS FOR TYPICAL EROSION CONTROL MATTING DETAIL INSTALL PER MANUFACTURERS SPECIFICATIONS.

B. APPLICATION AND THING.

B. APPLICATION AND THING.

D. DURING THE GROWING SEASON (APRIL 15 - SEPTEMBER 15 USE ON THE BASE OF GRASSED WATERWARS, STEEP SLOPES OF RASSED SIFE AND WELTANDS.

2. DURING THE LEFFALL AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED AND WINTER (SEPTEMBER 15 - APRIL 15) IN ADDITION TO THOSE LISTED

SIREAMS, AND WEILANDS.

DURING THE LATE FALL AND WINTER (SEPTEMBER 15 — APRIL 15) IN

ADDITION TO THOSE LISTED ABOVE USE ON SIDE SLOPES OF GRASSED

WATERWAYS AND MODERATE SLOPES (GREATER THAN 8%).

MAINTENANCE

1. INSPECT PERIODICALLY AND BEFORE AND AFTER STORM EVENTS TO ENSURE CONTACT WITH THE SOIL UNTIL 85% VEGETATIVE COVER IS ESTABLISHED. REPAIR AND RESTAPLE AS NECESSARY.

C. PERMANENT MULCHING CO. REPAIR AND RESIAPLE AS NECESSART.

1. WOOD CHIPS OR GROUND BARK
A. APPLY TO A THICKNESS OF 2 TO 5 INCHES. TYPICAL APPLICATION RATES
ARE 10-20 TONS/CRE OR 450-920 POUNDS/1,000 SF.
B. MAINTENANCE:

NTENANCE: INSPECT ANNUALLY AND AFTER RAIN EVENTS OF 2.5 INCHES OR MORE IN A 24 HOUR PERIOD. REPAIR/REPLACE AS NECESSARY.

2. EROSION CONTROL MA.

A. COMPOSITION OF THE MIX SHALL BE AS FOLLOWS:

1. ORGANIC MATTER CONTENT SHALL BE BETWEEN 25-65% DRY WEIGHT BASIS.

BASIS.

2. PARTICLE SIZE BY WEIGHT SHOULD BE 100% PASSING THE 3"

PARTICLE SIZE BY WEIGHT SHOULD BE 100% PASSING THE 3' SCREEN, 90-100% PASSING THE 0.75 INCH SCREEN, NO 100% PASSING THE 0.75 INCH SCREEN, AND 30-75% PASSING THE 0.25 INCH SCREEN, AND 10-75% PASSING THE 0.25 INCH SCREEN, THE DREADLE PRIVATE PROBLEM PROPRIOR SHALL BE LLONGATED AND TIBROUS. IT SHALL NOT CONTAIN WOOD AND BARK CHIPS, GROUND CONSTRUCTION DEBRIS, OR REPROCESSED WOOD PRODUCTS.

THE MIX SHALL NOT CONTAIN SILTS, CLAYS, OR FINE SANDS. SOLUBLE SALTS CONTENT SHALL BE < 4.0MMHOS/CM AND A pH OF

5.0-8.0

B. PLACEMENT OF BERM
1. PLACE BERM ALONG A LEVEL CONTOUR. BERM MUST BE A MINIMUM OF 12" HIGH ON THE UPHILL SIDE AND 2 FEET WIDE.
C. MAINTENANCE

NTENANCE
INSPECT PERIODICALLY AND AUGMENT AS NEEDED TO MAINTAIN INITIAL
THICKNESS. REPLACE IF NO LONGER FUNCTIONING AS INTENDED.

enc Supulsin	SOIL DRAINAGE				
	SEEDING MIXTURE	DROUGHTY	WELL DRAINED	MODERATELY WELL DRAINED	POORLY DRAINED
	A	FAIR	GOOD	GOOD	FAIR

USE	MIXTURE	DROUGHTY	DRAINED	WELL DRAINED	DRAINED
STEEP CUTS AND FILLS, BORROW AND DISPOSAL AREAS	<b>₹</b> BCD	FAIR POOR POOR FAIR	GOOD GOOD GOOD EXCELLENT	GOOD FAIR EXCELLENT EXCELLENT	FAIR FAIR GOOD POOR
WATERWAYS, EMERGENCY SPILLWAYS, AND	A	GOOD	GOOD .	GOOD	FAIR
OTHER CHANNELS WITH FLOWING WATER.	C	GOOD	EXCELLENT	EXCELLENT	FAIR
LIGHTLY USED PARKING LOTS, ODD AREAS,	A B C	G000	GOOD	GOOD	FAIR
UNUSED LANDS, AND LOW INTENSITY USE		G000	GOOD	FAIR	POOR
RECREATION SITES.		G000	EXCELLENT	EXCELLENT	FAIR
PLAY AREAS AND ATHLETIC FIELDS. (TOPSOIL,	E	FAIR	EXCELLENT	EXCELLENT	SEE NOTE
S ESSENTIAL FOR GOOD TURF.)	F	FAIR	EXCELLENT	EXCELLENT	SEE NOTE

SEED MIXTURE SELECTION BASED ON SOIL TYPE

NOTE: POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREAS AND ATHLETIC FIELDS

SEED MIXTURES FOR PERMANENT VEGETATION					
MIXTURE	SPECIES	POUNDS PER ACRE	POUNDS PER 1,000 SF		
A	Tall Fescue Creeping Red Fescue REDTOP TOTAL	20 20 2 42	0.45 0.45 0.05 0.95		
8	TALL FESCUE CREEPING RED FESCUE CROWN VEICH OR ELATIPEA 707AL	15 10 15  30 40 OR 55	0.35 0.25 0.35  0.75 0.95 OR 1.35		
С	TALL FESCUE CREEPING RED FESCUE BIRDSFOOT TREFOIL TOTAL	20 20 <u>B.</u> 48	0.45 0.45 0.20 1.10		
D	TALL FESCUE FLATPEA TOTAL	20 <u>30</u> 50	0.45 0.75 1.20		
E	CREPPING RED FESCUE KENTUCKY BLUEGRASS TOTAL	50 50 100	1.15 1.15 2.30		
F	TALL FESCUE	150	3.60		

## SOIL STOCKPILES

PLACE IN THE LOCATIONS SHOWN ON THE PLAN. ADDITIONAL STOCKPILES MUST BE LOCATED SO FEET FROM DITCHES AND CULVERT INLETS. OTECTION OF STOCKPILES PROTECT SOIL AND AGGREGATE STOCKPILES WITH TEMPORARY PERIMETER SEDIMENT BARRIER SUICH AS SILT FENCE OR SILT SOCK. COVER ACTIVE STOCKPILES WITH ANCHORED PROTECTIVE COVERING PRIOR TO EXPECTED STORM EVENTS. INACTIVE STOCKPILES SHALL BE COVERED WITH ANCHORED TAPPS OR TEMPORARTY SECRETAIN MULCHED PER THE TEMPORARTY MEGETATION AND MULCHED PER THE TEMPORARTY MEGETATION AND MULCHED PER THE TEMPORARTY MEGETATION AND MULCHED THAT STOCKPILES THAT ARE A SOURCE OF DUST SHALL BE COVERED.

# NIST CONTROL A. DUST SHALL BE CONTROLLED ON SITE DURING CONSTRUCTION BY IMPLEMENTING THE FOLLOWING DUST CONTROL MEASURES 1. MULCHING AND VEGETATIVE COVER TO REDUCE DUST. 2. MECHANICAL SWEEPERS AND FINE WATER SPRAYS. 3. COVER SURFACES WITH CRUSHED STONE OR COARSE GRAVEL.

PHASE 1 CONSTRUCTION SCUENCING MOTES

1. THIS PROJECT IS PROPOSED TO BE CONSTRUCTED IN TWO PHASES. THE NOTES OF THIS SECTION REFER TO PHASE I.

2. PHASE I INCLUDES THE REALIGNMENT AND RECONSTRUCTION OF A PORTION OF ST. MATTHEWS DR. AT THE SOUTHWEST CORNER OF THE PARCEL. THE LENGTH OF ROAD TO BE RECONSTRUCTION OF APPROXIMATELY 450 FT. THIS PHASE ALSO INCLUDES THE CONSTRUCTION OF APPROXIMATELY 450 FT. THIS PHASE ALSO INCLUDES THE CONSTRUCTION OF APPROXIMATELY 500 FT OF SHARED DRIVEWAY ACCESS FOR LOTS 9 AND 10.

3. THE COMMON DRIVEWAY CONTION SHALL PROCEED FIRST TO MINIMIZE DAMAGE TO ANY PROPOSED WORK IN ST. MATHEWS DRIVE.

4. INSTALL ALL TEMPORARY EROSON CONTROL MEASURES AS SHOWN ON THE PLANS PRIOR TO START OF CONSTRUCTION.

5. CLEAR/GRUB ONLY WITHIN THE LIMITS OF GRADING AS SHOWN ON THE PLANS REMOVE STUMPS ONLY FROM THOSE AREAS THAT CAN BE WORKED AND STABILIZED WITHIN 45 DATS OF REMOVES THOSE AREAS THAT CAN BE WORKED AND STABILIZED STABILIZED CONSTRUCTION ENTRANCE. CONSTRUCTION STABILIZED. CONSTRUCTION OF TREATER.

A. STOCKPILE LOAM IN LOCATION(S) SHOWN ON THE PLANS FOR RE-USE AS

A. SICCHPILE LOAM IN LOCATION(S) STORMS OF THE PERSON OF THE PROPOSED 48"

2. WILCH — FROM SEPTEMBER 15TH TO MAY 1ST

2. WILCH — TROU SEPTEMBER 15TH TO MAY 1ST

9. BEGIN DRIVEWAY CONSTRUCTION WITH THE INSTALLATION OF THE PROPOSED 48"

9. BIGON ORVEWAY CONSTRUCTION WITH THE INSTALLATION OF THE PROPOSED 48"

10. CULVERT INSTALLATION SHALL BE COMPLETED OURING LOW FLOW CONDITIONS

11. THE CULVERT SHALL ARE INSTALLED TO THE LINE AND GRADES AS SHOWN ON THE
DESIGN PLANS.

12. THE BEDDING AND BACKFILL MATERIALS SHALL BE INSTALLED AND COMPACTED IN
ACCORDANCE WITH THE CONSTRUCTION DETAILS.

13. THE DESIGN ENGINEER SHALL INSPECT THE SOIL CONDITIONS AT THE SITE PRIOR
TO THE PLACEMENT OF THE BEDDING AND CULVERT. UNSUITABLE MATERIALS

SHALL BE REMOYED AND REPLACED WITH SUITABLE BEDDING MATERIAL APPROVED

THE ENGINEER.

19. THE ENGINEER.

19. THE ENGINEER.

19. THE SOCKFIL MATERIAL IS OVER THE CROWN OF THE CULVERT TO A MINIMUM
PROCECO.

19. CONSTRUCT AND STABILIZE ALL PERMANENT SEDIMENT, EROSION, AND DETENTION
CONTROL FACILITIES AS SHOWN.

10. SHARED DRIVEMAY CONSTRUCTION

11. CONSTRUCT AND STABILIZE ALL PERMANENT SEDIMENT, EROSION, AND DETENTION
CONTROL FACILITIES AS SHOWN.

1. CONSTRUCT IN LOCATION(S) AND TO GRADES AS SHOWN ON THE PLANS

2. FILLS:

1. CONSTRUCT IN LOCATION(S) AND TO GRADES AS SHOWN ON THE PLANS

2. FILLS:

2. FILLS:

3. PLACE MAXIMUM 12" LIFTS AND COMPACT TO 95% MAXIMUM DRY

A PLACE MAYIMIM 12" HETS AND COMPACT TO 95% MAYIMIM DRY

A. PLACE MAXIMUM 12" LIFTS AND COMPACT TO 95% MAXIMUM DRY DENSITY.

B. ALL MATERIAL BASED ON PROCTOR TEST SHALL BE FREE OF DELETERIOUS MATERIAL SUCH AS LOAM, STUMPS, BRUSH, AND ROCKS LARGER THAN 3/4 THE DEPTH OF THE LIFT BEING PLACED.

J. LOAM AND SEED SLOPES WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

B. BASE MARRALS.

B. BASE MATERIALS:

1. BANK RUN AND CRUSHED GRAVEL SHALL BE PLACED IN 6" LIFTS AND COMPACTED TO 95% MAXIMUM DRY DENSITY TO THE DEPTHS SPECIFIED IN THE SHARED DRIVE CROSS SECTION.

17. ONCE DRIVEWAY CONSTRUCTION IS COMPLETED TO CRUSHED GRAVEL GRADE, BEGIN RECONSTRUCTION OF ST. MANTHEWS DRIVE.

18. THE TOWN DPW SHALL BE PROVIDED ADEQUATE NOTIFICATION PRIOR TO BEGINN CONSTRUCTION. TEMPORARY ROADWAY CLOSURE MAY BE REQUIRED DURING THE CONSTRUCTION.

CONSTRUCTION. IEMPURANT RODURN.

19. REMOVE ORGANICS, RIPRAP, STONEWALLS, AND ANY OTHER UNSUITABLE MATERIALS FROM THE GRADING LIMITS AS SHOWN ON THE PLANS FOR THE RECONSTRUCTION OF ST. MATTHEWS DRIVE.

20. ST. MATTHEWS DRIVE ROAD RECONSTRUCTION

A. CUTS AND FILLS:

ADMITTANCE IN I OCATION(S) AND TO GRADES AS SHOWN ON THE

1. CONSTRUCT IN LOCATION(S) AND TO GRADES AS SHOWN ON THE PLANS 2. FILLS: A. PLACE MAXIMUM 12" LIFTS AND COMPACT TO 95% MAXIMUM DRY

DENSITY.

B. ALL MATERIAL BASED ON PROCTOR TEST SHALL BE FREE OF DELETERIOUS MATERIAL SUCH AS LOAM, STUMPS, BRUSH, AND ROCKS LARGER THAN 3/4 THE DEPTH OF THE LIFT BEING PLACED.

3. LOAM AND SEED SLOPES WITHIN 72 HOURS OF ACHIEVING FINISHED

GRADE.

B. DRAINAGE AND UTILITY STRUCTURES

1. INSTALL' AS NECESSARY AND STABILIZE.

C. BASE MATERIALS:

1. INSTALL AS NECESSARY AND STABILIZE.

C. BASE MATERIALS:

1. BANIK RUN AND CRUSHED GRAVEL SHALL BE PLACED IN 6" LIFTS AND COMPACTED TO 95% MAXIMUM DRY DENSTY TO THE DEPTHS SPECIFIED IN THE 5T. MATTHEWS DRIVE CROSS SECTION.

D. PAVEMENT FOR ST. MATTHEWS DRIVE AND SHARED DRIVE

1. PLACE AS SOON AS "POSSIBLE AFTER THE SELECT MATERIALS ARE

2. STABILIZE ALL ROADWINS, PARKING AREAS, AND SON
WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.

21. INSPECT, MANITAIN, AND IF NECESSARY, REPAIR ALL EROSION AND SEDIMENT
CONTROL MEASURES AS STATED IN EROSION CONTROL NOTES ON THIS SHEET.

22. RELIVOR ALL TEMPORARY EROSION CONTROL NOTES ON THIS SHEET.

25. STABLISHED.

PHASE 2 CONSTRUCTION SECUENCING MOTES

1. THIS PROJECT IS PROPOSED TO BE CONSTRUCTED IN TWO PHASES. THE NOTES OF
THIS SECUENT REFER TO PHASE 2.

2. PHASE 2 INCLUDES THE CONSTRUCTION OF THE PROPOSED 1,000 FT OF ROADWAY
AND CUL-DE-SAC DESIGNATED AS HERITAGE LANE.

3. INSTALL ALL TEMPORARY EROSON CONTROL MEASURES AS SHOWN ON THE PLANS
PRIOR TO START OF CONSTRUCTION.

4. CLEAR/GRUB CNLY WITHIN THE LIMITS OF GRADING AS SHOWN ON THE PLANS.
REMOVE STUMPS ONLY FROM THOSE AREAS THAT CAN BE WORKED AND STABILIZED
WITHIN 45 DAYS OF REMOVAL.

WITHIN 45 DAYS OF REMOVAL

5. CLEAR/GRUB

A. STUMPS SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH LOCAL AND
STATE REGULATIONS.

6. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE. CONSTRUCT IN LOCATION(S)
SHOWN ON THE PLANS AND PER THE STABILIZED CONSTRUCTION ENTRANCE DETAIL.
7. STOCKPILES

A. STOCKPILE LOAM IN LOCATION(S) SHOWN ON THE PLANS FOR RE-USE AS

A. STOCKPILE LOAM IN LOCATION(S) SHOWN ON THE PLANS FOR RE-USE AS NECOCO.

B. TEMPORARILY STABILIZE LOAM STOCKPILES WITH:

1. WINTER RYE GRASS — PRIOR TO SEPTEMBER 15TH

2. MULCH — FROM SEPTEMBER 15TH TO MAY 1ST

CONSTRUCT AND STABILIZE ALL TEMPORARY AND PERMANENT SEDIMENT, EROSION, AND DETENTION CONTROL FACILITIES AS LISTED ABOVE.

A. THESE SHALL BE INSTALLED BEFORE ANY MAJOR EARTH MOVING OPERATIONS: HERITAGE LANE ROAD CONSTRUCTION

A. CUTS AND FILLS:

1. CONSTRUCT IN LOCATION(S) AND TO GRADES AS SHOWN ON THE PLANS 2. FILLS:

A. PLACE MAXIMUM 12" LIFTS AND COMPACT TO 95% MAXIMUM DRY DENSITY.

B. ALL MATERIAL BASED ON PROCTOR TEST SHALL BE FREE OF DELETERIOUS MATERIAL SUCH AS LOAM, STUMPS, BRUSH, AND

DELETERIOUS MATERIAL SUCH AS LOAM, STUMPS, BRUSH, AND
ROCKS LAGGER THAN 3/4 THE DEPTH OF THE LETT BEING PLACED.
3. LOAM AND SEED SLOPES WITHIN 72 HOURS OF ACHIEVING FINISHED
GRADE.
B. DRAINAGE AND UTILITY STRUCTURES
1. INSTALL AS SHOWN IN ACCORDANCE WITH DETAILS AND DRY STABILIZE.
C. BASE MATERIALS: 1. BANK RUN AND CRUSHED GRAVEL SHALL BE PLACED IN 6" LIFTS AND COMPACTED TO 95% MAXIMUM DRY DENSITY TO THE DEPTHS SPECIFIED IN THE HERITAGE LANE CROSS SECTION.

D. PAVEMENT

D. PAVEMENT

1. PLACE AS SOON AS POSSIBLE AFTER THE SELECT MATERIALS ARE INSTALLED AND ACCEPTED TO ELIMINATE SOIL EROSION.

2. STABILIZE ALL ROADWAYS AND DRIVES WITHIN 72 HOURS OF ACHIEVING THISHED GRAD THE SOIL FROSTON.

10. INSPECT, MAINTAIN, AND IF NECESSARY, REPAIR ALL EROSION AND SEDIMENT CONTROL MEASURES STATED IN EROSION CONTROL NOTES ON THIS SHEET.

11. REMOVE ALL TEMPORARY EROSION CONTROL MORES ONCE INITIAL GROWTH IS ESTABLISHED.

ESTABLISHED.

STOCKPLED MATERIALS CONSTRUCTION SECLENCING MOTES

1. THE EXISTING MATERIAL STOCKPILE ON THE EAST SIDE OF THE INTERSECTION OF GERRIOR LANE AND ST. MATTHEWS DRIVE WILL BE PROCESSED ON-SITE AND USED FOR CONSTRUCTION OF THE ROADS AND DRIVEWAYS.

2. EROSION CONTROL MEASURES SHALL BE INSTALLED AS SHOWN ON THE MATERIAL PROCESSING STEP PLAK AREA SHOWN ON THIS PLAN TO BE USED FOR PROCESSING AND STOCKEPIPING PROCESSED MATERIAL.

3. AND STOCKEPIPING PROCESSED MATERIAL.

4. LOAM SHALL BE STOCKPLIED IN THE LOCATION SHOWN ON THIS SITE PLAN.

5. ALL FILL AND GRAVEL MATERIAL FOR THE PROPOSED SUBDIVISION PROLECT WILL BE PROCESSED FOR THE EXISTING STOCKPILE ANY EXCESS PROCESSED GRAVEL WILL BE REMOVED FROM THE SITE.

6. THE ESTIMATED QUANTITY OF MATERIAL TO BE PROCESSED FROM THE ON-SITE STOCKPILE IS 10,000 TO 12,000 CY. THE APPROXIMATE QUANTITY OF MATERIAL REQUIRED FOR THE DEVELOPMENT IS SOSX. THE REMAINDER OF THE PROCESSED MATERIAL WILL BE REMOVED FROM THE SITE.

## ADDITIONAL NOTES

NO FUEL SHALL BE STORED ON SITE DURING CONSTRUCTION.
 DURING CONSTRUCTION DUST SHALL BE FREVENTED FROM BECOMING A SAFETY OR HEALTH HAZARD BY THE IMPLEMENTATION OF ACCEPTED CONTROL METHODS SUCH AS

2. DUMINI LOURING LOUR SHALL BE PREVENTED FROM BECOMING A SPETT OF MANUAL PRIVATE PROPERTY OF THE IMPLEMENTATION OF ACCEPTED CONTROL METHODS SUCH AS WATERING.

3. ALL CONSTRUCTION MATERIALS THAT ARE SPILLED OR DEPOSITED ON THE PUBLIC RODAWAYS SHALL BE REMOVED BY THE CONTRACTOR.

4. DO NOT BEGIN CONSTRUCTION UNTIL ALL LOCAL, STATE, AND FEDERAL PERMITS HAVE BEEN APPLED FOR AND RECEVED.

5. IF, DURING CONSTRUCTION, IT BECOMES APPARENT THAT DEFICIENCIES EXIST IN THE APPROVED DESIGN DRAWINGS, THE CONTRACTOR SHALL BE REQUIRED TO CORRECT THE DEFICIENCIES TO MEET THE REQUIREMENTS OF THE REGULATIONS AT NO EXPENSE TO THE TOWN.

5. REQUIRED EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY DISTURBANCE OF. THE SITE'S SUFFACE AREA AND SHALL BE MANTANNED THROUGH THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES. IF, DURING CONSTRUCTION, IT BECOMES APPARENT THAT ADDITIONAL EROSION CONTROL MEASURES ARE REQUIRED TO STOP ANY EROSION ON THE CONSTRUCTION SITE DUE TO ACTUAL SITE CONDITIONS, THE OWNER SHALL BE REQUIRED TO INSTALL THE NECESSARY EROSION PROTECTION AT NO EXPENSE TO THE TOWN.

7. ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL CONFORM TO TOWN OF BARRINGTON SUBDIVISION REQUIRIONS AND THE LATEST EDITION OF THE NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATIONS FOR ROAD & BRIDGE CONSTRUCTION.

LAND USE OFFICE

RECEIVED

S/15/13 AS SHOWN MS/MJS MS DATE: SCALE: DESIGNED BY: DRAWN BY: APPROVED BY:

DETAILS TRUST JBDIVISION BARRINGTO ы RUCTION LAN OR HOMEST ERRIOR GERRI

> C Ĭ.

=

SE SE

TEAD DRIVI

MJS ENGINEERING, JOB: 11-060

## SECTION B-B' GRAVEL WETLAND PIPE OUTLET DETAIL SCALE: 1"=5"

- DO NOT PLACE GRAVEL WETLANDS INTO SERVICE UNTIL THE BMI HAS BEEN PLANTED AND ITS CONTRIBUTING AREAS HAVE BEEN FULLY STABILIZED.

- 5. THE BERN SHALL BE CONSTRUCTED BEGINNING FROM THE LOWEST POINT UNIFORMLY ALONG ITS ENTIRE LENGTH. PLACE MATERIALS IN MAXIMUM 12 LOOSE LIFTS COMPACTED TO 95% MAXIMUM MODIFIED PROCTOR DENSITY. EMBANKMENT SOIL. SHALL HAVE NO ORGANIC MATTER OR FROZEN MATERIAL AND NO STONES LARGER THAN 2/3 OF THE MAXIMUM LOOSE LIFT THICKNESS. STONES AROUND ANY STRUCTURES AND/OR CONDUITS SHALL NOT EXCEED 3 INCHES. EMBANKMENT FILL MATERIAL SHALL HAVE THE FOLLOWING GRADATION:

- ALL DISTURBED AREAS NOT OTHERWISE PLANTED SHALL RECEIVE FOUR INCHES OF LOAM AND SEEDED PER THE CONSTRUCTION SEQUENCING AND EROSION CONTROL NOTES ON SHEET D1.


SCUULNING AND ERUSION CONTROL NOTES ON SHEET DI.

GRAVEL WETLAND MAINTENANCE:

1. SYSTEMS SHOULD BE INSPECTED AT LEAST TWICE ANNUALLY,
AND FOLLOWING ANY RAINFALL EVENT EXCEEDING 2.5 NICHES IN
A 24 HOUR PERIOD, WITH MAINTENANCE OR REHABILITATION
CONDUCTED AS WARRANTED BY SUCH INSPECTION.

2. TRASH AND DEBRIS SHOULD BE REMOVED AT EACH INSPECTION.

3. AT LEAST ONCE ANNUALLY, SYSTEM SHOULD BE INSPECTED FOR
DRAWDOWN TIME. IF GRAVEL WETLAND DOES NOT DRAIN WITHIN
72-HOURS FOLLOWING A RAINFALL EVENT, THEN A QUALIFED
PROFESSIONAL SHOULD ASSESS THE CONDITION OF THE FACILITY
TO DETERMINE MEASURES REQUIRED TO RESTORE FILTRATION
FUNCTION INCLUDING BUT NOT LIMITED TO REMOVAL AND
REPLACEMENT OF WETLAND SOIL AND REPLANTING.
4. VEGETATION SHOULD BE INSPECTED AT LEAST ANNUALLY, AND
MAINTAINED IN HEALTHY CONDITION, INCLUDING PRUNNING,
REMOVAL AND REPLACEMENT OF DEAD OF DISEASED VEGETATION,
AND REMOVAL OF INVASIVE SPECIES.



## CROSS SECTION DETAIL

NOTES:


1. RIP RAP SPILLWAYS ARE LOCATED AT SEDIMENT FOREBAY OUTLETS, BETWEEN CELL #1 AND CELL #2 OF GRAVEL WETLAND AND EMERGENCY SPILWWAY OF GRAVEL WETLAND.

## RIP-RAP GRADATION

% OF WEIGHT SMALLER	SIZE OF STONE			
THAN THE GIVEN SIZE				
100	- 6	TO	. 8	
85	5.2	. TO	7.2	
50	4	TO	6	
15	1.2	70		

## SEDIMENT FOREBAY TYPICAL CROSS SECTION DETAIL


- NOIS:
  1. REFER TO BERM CONSTRUCTION NOTES IN GRAVEL WETLAND
  DETAIL FOR BERM CONSTRUCTION REQUIREMENTS.
  2. REFER TO RIPRAP SPILLWAY CROSS SECTION DETAIL FOR
  SPILLWAY CONSTRUCTION REQUIREMENTS.
  3. THE SEDIMENT FORBERY SHALL BE MOWED WITH THE REST OF
  THE SITES LAWN AREAS TO PROMOTE HEALTHY GROWTH AND
  PREVENT THE ENCROACHMENT OF WEEDS AND WOODY
  4. WESTALL STAFF GAGE TO MEASURE SEDIMENT ACCUMULATION.
  SEDIMENT SHALL BE REMOVED AFTER SEDIMENT ACCUMULATION.
  SEDIMENT SHALL BE REMOVED AFTER SEDIMENT ACCUMULATION.



## **GRAVEL WETLAND #1 CROSS SECTION**

WETLAND SOIL MIX SHALL BE A SILT LOAM WITH A MINIMUM OF 15-20% ORGANIC CONTENT BY MASS. THE CLAY CONTENT SHALL NOT EXCEED 15% BY VOLUME. THE ORGANIC MATTER SHALL CONSIST OF DECIDUOUS LEAF COMPOST PROPERLY MATURED AND AT LEAST ONE YEAR OLD. THERE SHALL BE NO LEAF MULCH, COMPOSTED MIXED YARD DEBMIS, OR WOOD CHIPS.

2. GRAVEL WETLAND BOTTOM TO BE PLANTED WITH NEW ENGLAND WETLAND MIX AVAILABLE FROM:



## **GRAVEL WETLAND OUTLET CONTROL STRUCTURE:** 36" NYLOPLAST WEIR STRUCTURE DETAIL

LAND USE OFFICE.

1. PVC DRAIN BASIN TO BE NYLOPLAST 36 INCH WEIR STRUCTURE
OR APPROVED EQUAL, FRAME AND COVER SHALL BE NYLOPLAST
24 INCH PEDESTRIAN H-10 STANDARD LOCKING GRATE ASSEMBLY
OR APPROVED EQUAL.

2. FOR SALES, CONTACT:
HANCOR
GEOFF HUBBARD — (603) 988—7593
68 SOUTH STREET
PORTSMOUTH, NH 03801

RECEIVED

3. TRASH RACK AVAILABLE FROM: CONTECH 200 ENTERPRISE DR. SCARBOROUGH, ME 04074 PHONE: 207-885-9830

IOB: 11-060


LANE


GERRIOR

PC

MJS ENGINEERING,


CONSTRUCTION






STONE CHECK DAM

PROFILE VIEW





- CONSTRUCTION SPECIFICATIONS:

  1. STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE APPROPRIATE SPACING:

  2. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION, AIR AND WATER POLLUTION WILL BE MINIMIZED.

  3. STRUCTURES SHALL BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS BEEN COMPLETED.

- MAINTENANCE NOTES:

  1. TEMPORARY GRADE STABILIZATION STRUCTURES SHOULD BE INSPECTED AFTER EACH STORM AND DAILY DURING PROLONGED STORM EVENTS. ANY DAMAGE TO THE STRUCTURES SHALL BE REPAIRED IMMEDIATELY.

  2. PARTICULAR ATTENTION SHOULD BE GIVEN TO END RUN AND EROSION AT THE DOWNSTREAM TOE OF THE STRUCTURES.

  3. WHEN REMONING THE STRUCTURES, THE DISTURBED AREAS SHALL BE BROUGHT UP TO EXISTING CHANNEL GRADE AND THE AREAS PREPARED, SEEDED AND MULCHED.

  4. SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURES WHEN IT REACHES 1/2 THE ORIGINAL HEIGHT OF THE STRUCTURE.

VARIES

## VEGETATED TREATMENT SWALE DETAIL


CONSTRUCTION NOTES:

1. REFER TO BERM CONSTRUCTION NOTES IN GRAVEL WETLAND DETAIL FOR BERM CONSTRUCTION REQUIREMENTS.

2. SWALE SHALL HAVE GREATER THAN 85% VEGETATIVE GROWTH PRIOR TO RECEIVING RUNDFF.

- 2. PERFORM PERIODIC MOWING. DO NOT MOW GRASS SHOWLER THAN 4 INCHES.
  3. REMOVE DEBRIS AND ACCUMULATED SEDIMENT BASED ON INSPECTION.
  4. REPAIR ERODED AREAS, REMOVE INVASIVE SPECIES AND DEAD VEGETATION, AND RESEED WITH APPLICABLE GRASS MIX AS WARRANTED BY INSPECTION.

## STONE CHECK DAM



GEOTEXTILE FABRIC


- 1. CONSTRUCTION TO BE IN ACCORDANCE WITH PSNH CONSTRUCTION STANDARDS FOR NEW ELECTRICAL SERVICE WORK BY CONTRACTORS, MOST RECENT EDITION.


  1. SELECT SAND BACKFILL SHALL CONSIST OF A PINE GRANLLAR MATERIAL OF WHICH TOOK SHALL PASS THROUGH A 1/4" SIEVE. EXCEPT NATURALLY OCCURING SMOOTH FOUND PEDBELS NO GREATER THAN 3/5" IN DIMETER ARE PERMITTED AS LONG AS THEIR TOTAL VOLUME PER CUBIC POOT OF SAND DOES NOT EXCEED 1%. THE SAND SHALL BE COMPLETELY FREE OF FROZEN LUMPS, ROCKS, STONES, DERRIS AND RUBBISH. BACKFILL SHALL BE THOROUGHLY COMPACTED IN 6" LIETS.

  3. CONDUIT SIZES TO BE 5" 3" 3-PHASE PRIMARY AND 4" 3-PHASE SECONDARY. ALL CONDUIT SIZES TO BE VERIFIED BY PSNH.

  4. ALL CONDUIT INSTALLATIONS MUST CONFORM TO THE CURRENT EDITION OF THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND WHERE APPLICABLE THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES, AND WHERE APPLICABLE THE NATIONAL ELECTRIC SAFETY CODE, STATE AND LOCAL CODES AND ORDINANCES,

## TELEPHONE & ELECTRIC TRENCH





## RIP-RAP GRADATION | X OF WEIGHT SMALLER | SIZE OF STONE | THAN THE GIVEN SIZE | (INCHES) | 100 | 6 | TO | 8 | 85 | 5.2 | TO | 7.2



- CONSTRUCTION SPECIFICATIONS:

  1. PREPARE THE SUB-GRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC, AND RIP-RAP 10 THE GRADES SHOWN ON THE PLANS.

  2. MINNIUM 6° SAND/GRAVEL BEDDING OR GEOTEXTILE FABRIC REQUIRED UNDER ALL ROCK RIP-RAP.

  3. THE ROCK OR GRAVEL USED FOR FILTER OR RIP-RAP SHALL CONFORM TO THE SPECIFIED GRADATION.

  4. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF ROCK RIP-RAP.

  5. STOME FOR PROTECTION THE FABRIC SHALL BE REPROTECTED AND COMPLETE THE CHARACTERY OF PLACEMENT OF RECOVERY OF THE RIP-RAP CHARACTERY OF PLACEMENT OF THE CHARACTERY OF PLACEMENT OF SHALL BE CONFIRMED BY PLACEMENT OF FABRIC OVER THE CHARACTERY OF THE RIP-RAP CHARACTERY OF THE RIP-RAP CHARACTERY OF THE RIP-RAP MAY BE PLACED BY SCHOLING FOR REPARE THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

  6. RIP-RAP SIZE CHOSEN FOR THE WORST CASE OF ALL OUTLETS. ALL RIP-RAP USED FOR PIPE OUTLET PROTECTION WILL HAVE THE SAME GRADATION AND THICKNESS.


- MAINTENANCE NOTES:

  1. OUTLETS SHALL BE INSPECTED AND CLEANED ANNUALLY AND AFTER ANY MAJOR STORM EVENT. ANY EROSION OR DAMAGE TO THE RIP—RAP SHALL BE REPAIRED IMMEDIATELY.


  2. THE CHANNEL IMMEDIATELY DOWNSTREAM FROM THE OUTLET SHOULD BE CHECKED TO SEE THAT NO EROSION IS OCCURRING.

  3. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.

PIPE OUTLET PROTECTION DETAIL NOT TO SCALE



STANDARD DRAINAGE PIPE TRENCH



- PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP's), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
  NOTE: WHEN USING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH PAPER SIDE DOWN.
- 2. BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE RECP's IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH WITH APPROXIMATELY 12" (30 CM) OF RECP'S EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP'S WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN THE BOTTOM OF THE TRENCH. BACKFUL AND COMPACTED THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30 CM) PORTION OF RECP'S BACK OVER SEED AND COMPACTED SOIL. SECURE RECP'S OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30 CM) ACROSS THE WIDTH OF THE RECP'S.
- ACROSS THE WIDTH OF THE RECP'S.

  3. ROLL CENTER RECP'S IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. RECP'S WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECP'S WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE.

  WHEN USING THE DOT SYSTEM", STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.

  4. PLACE CONSECUTIVE RECP'S END OVER PAID (SHINGLE STYLE) WITH A 4" 6" (10 CM -15 CM) OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER TO SECURE RECP'S.
- 5. FULL LENGTH EDGE OF RECP's AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
- 6. ADJACENT RECP'S MUST BE OVERLAPPED APPROXIMATELY 2" 5" (5 CM -12.5 CM) (DEPENDING ON RECP'S TYPE) AND STAPLED.
- 7. IN HIGH FLOW CHANNEL APPLICATIONS, A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT (9 M 12 M) INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10 CM) APART AND 4" (10 CM) ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL
- 8. THE TERMINAL END OF THE RECP's MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30 CM) APART IN A 6" (15 CM) DEEP X 6" (15 CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
- . IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 CM) MAY BE NECESSARY TO PROPERLY ANCHOR THE RECP'S.




A. OVERLAPS AND SEAMS.
B. PROJECTED WATER LINE
C. CHANNEL BOTTOM/SIDE
SLOPE VERTICES

\*\* IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 5" (15 cm) MAY BE REQUIRED.

## TYPICAL TURF REINFORCEMENT MATTING DETAIL

NOTES:

1. FOR SALES CONTACT:
EJ PRESCOTT, INC.
210 SHEEP DAVIS RD.
CONCORD, NH
603-224-9545



REGULAR FLOW SILTSACK . (FOR AREAS OF LOW TO MODERATE PRECIPITATION AND RUN-OFF)


300 LBS NOTE 20 X NOTE 20 LBS 80 PSI 120 LBS 80 X 40 US SIEVE 40 GAL/AMN/SO FT 0.55 SEC -1

2, FILTER TRAPS SHALL BE INSPECTED AFTER EVERY RAIN EVENT OF 0.25° OR OREATER AND SEDIMENTS SHALL BE REMOVED FROM TRAP WHEN SEDIMENT HAS REACHED TWO THIRDS OF THE DEPTH OF THE TRAP, OR IF PONDING OF WATER AT SURFACE BEGINS TO OCCUR. DO NOT PUNCTURE FILTER TRAP TO MITIGATE PONDING.

LAND USE OFFICE"

CATCH BASIN GEOSYNTHETIC SILT SACK

RECEIVED



Į.

PC

MJS ENGINEERING,

JOB: 11-060