

TAX MAP 215 LOT 1 RIVER'S PEAK RESIDENTIAL DEVELOPMENT

OWNER/APPLICANT:

CABERNET BUILDERS P.O. BOX 291 STRATHAM, N.H. 03885



LOCATION MAP



WETLAND/SOIL CONSULTANT:

GOVE ENVIRONMENTAL SERVICES INC.

8 CONTINENTAL DRIVE,

BLDG 2 UNIT H

EXETER, NH 03833

1-603-778-0644



PRIOR STATE APPROVALS:

HDES STATE SUBDIVISION APPROVAL #: SA2005005120-A DATED 9/26/2
HDES SITE SPECIFIC PERMIT #: WPS 7162A DATED 2/6/20

<u>NEW STATE APPROVALS:</u>

NHDES STATE SUBDIVISION APPROVAL #: SA2013.

CIVIL ENGINEERS:



LAND SURVEYORS:



<u>INDEX</u>


TITLE SHEET	
PROPOSED SUBDIVISION	1-2
TOPOGRAPHIC PLAN	3-4
SUBDIVISION SITE PLAN	5
PLAN & PROFILES	6-8
DRAINAGE DETAILS	9
CONSTRUCTION DETAILS	10
CISTERN DETAILS	11
EROSION & SEDIMENT CONTROL DETAILS	12
I AND USE OFFICE	


DEC 23 2013


RECEIVED

PLAN SET LEGEND


UTILITY POLE	മ	FENCING	x
EXISTING LIGHT POLE	ф	'DRAINAGE LINE	p
EXISTING CATCH BASIN		STONE WALL	~~~~~~~
EXISTING HYDRANT	**	TREE LINE	\dots
SINGLE POST SIGN		ABUT. PROPERTY LINES	
PINES, ETC.	*	EXIST. PROPERTY LINES	
MAPLES, ETC.	83	BUILDING SETBACK LINES	
EXIST. SPOT GRADE	96x69	EXIST. CONTOUR	
PROP. SPOT GRADE	€6x69	PROP. CONTOUR ,	
TEST PIT	3 "	SOIL LINES	• • • • • • • • • • • • • • • • • • • •










<u>:</u>











RECEIVED












PREPARED FOR:

CABERNET BUILDERS P.O. BOX 929 STRATHAM, N.H. 03885


BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863



SECTION OF GRAVEL WETLAND

NOT TO SCALE



EROSION CONTROL BLANKET (ENKAMAT OR EQUAL) INSTALLATION

NOT TO SCALE

TO BE USED ON ALL 2:1 SIDES SLOPES AND ROADSIDE SWALES AT STATIONING SHOWN BELOW.

SITE PREPARATION: WETHER SLORG OR CHANGE, THE SIZE SEET SEE SHAPED TO THE DESIGN SPECIFICADES (GRADE, CEDICIET, DURSTLY OF SOIL, ITEL). AND THEN DRESSED TO BE FREE
SOIL CLOSE, CLUMPE, ROOKE, ON VONCE SHIPMET OF MYT SIGNERANT SEET THAT SOULD PREPARE SHE CHANGE (OR DELINE). FROM LYBO FRIEND TO SURFACE CONTINUES.

2. ANCHOR TRENCH: MOVER TROUGES ARE REQUIRED TO SECRELY FASTER HE DRAWAT (OR EDUA) TO the ondide drawat, in chieval, anchol the retination of the control and interest and the process of the control and processor of red control and designation and definition of the control and designation of the control and

3. ENKAMAT (OR EQUAL) INSTALLATION: NOL HE DIMENT (OR BOUN) DOWN HE BLOFT OR GOVERN. HE CONTROL PETROD ROLLS IS 3 TO 4 HOUSE. HE SPACE RETAINED HOLLS IS SHOWN IN DIFFER SHOWN IN THE SHOWN HOLD IN HE DESCRIBE OF WINE ROLLS EXHILD SHOWN IN SHOWN HOLD OF 3 TO 5 THE. SHOWN HOLD OF 3 HOUSE SHAVES HE ANALOGY OF SHAVES HOLD OF SHAVES HOUSE SHAVE SHAVE OF SHA

LINN'S DISTALL, THO ROUG OF STAPLES SPACED T.S. v. L.S. PEET APART AT ALL ROLL SPLICE LOCATIONS.

4. ANCHORING DEVICES: THICKLY III-8 CHUST OF A 6" x 1" x 6" METAL STAFFE METAL STAFFE METAL STAFFE SELL COMMISSION AND LOOSE, MSS 5" x 1" x 6" OR 12" x 1.5" x 12" METAL STAFFE METAL STAFF

5. SOR, FILLING: There are two offices used intolling devalue of model, and reliand on index-sort reliand, so, reliand devalued, or of the office are two devalued reliands in the manufacture devalued reliands seek used in matter at profited and index the confident profit of reliands seeked to the manufacture of the reliand seeked to the reliand to the reliand seeked to the reliand seeked to the reliand to the reliands to the reliands to the reliand to the reliands to the reliands

TOPISM. IF DAL PLUMS SED MER PLUMS IS COMPATED, YOU MAY AND SED SETTING MEM AND SOL, PLUMS IS COLOR. A SETTIO EXPLANATION FOR TEXTIFIANCE HIS RESPONSE FOR SERVICIAL PLUMS SED MEMOR TO SERVICIAL SECTION OF THE PROPERTY OF T

ALL INSTRUCE SOILS WILL BE FINAL GRADED, LOAMED, AND SEEDED HANEDIATELY AFTER CULVERTS AND HEADWALLS ARE PUND BACKFILED.

- 2. ALL OF THE SIDE SLOPES WILL BE LINED WITH JUTE MATTING TO AID IN THE STABILIZATION OF THE SOIL AND SEED.
- 3. ALL OF THESE CROSSINGS WILL BE PROTECTED WITH SILT FENCING, HAY BALES AND ORANGE CONSTRUCTION FENCING

4. DURING CONSTRUCTION OF ALL WETLAND CROSSINGS AND AT THE ENTRANCE OFF TO ROUTE 16, THE OWNER AND/OR THE TOWN OF BARRANCHON HILL HAVE A QUALIFIED REPRESENTATIVE ON-SHE TO INSPECT THE PROCESS AND VERIFY THAT ALL THE PROPER EFFORTS HAVE BEEN MADE TO MINIMIZE OR ELIMINATE PURIFIER INFOCT TO THE ADJACENT WETLAND.

5. THE VECETATED TREATMENT SWALE ADJACONING HOUTE IS WILDELINE WILSON FROM HEAD SEEDED, TO PROVIDE INSTANT STABILIZATION.



		·
	······································	
REVISIONS:		DATE

CONSTRUCTION DETAILS D2

PLAN FOR: RESIDENTIAL DEVELOPMENT BOULDER DRIVE BARRINGTON, NH

L	DATE:	DEC.	2013	***	SCAL	E: N	TS		
	PROJ.	NO:	NH-193		SHEET	NO.	10A	OF	12
								_	_

CISTERN SPECIFICATIONS

- 1. THE CISTERN SHALL BE DESIGNED TO BE TROUBLE FREE, AND IT SHALL BE DESIGNED TO LAST 50 YEARS.
- TO LAST 30 TEARS.

 THE MINIMUM CAPACITY SHALL BE 10,000 GALLONS. DEPENDING ON THE DEVELOPMENT LAYOUT/CONFIGURATION, ADDITIONAL GALLON REQUIREMENTS MAY BE IMPOSED AT THE DISCRETION OF THE FIRE CHIEF. ALL EXCEPTIONS, ADDITIONS, OR
- DELETIONS WILL BE IN WRITING.

 3. THE SUCTION CAPACITY SHALL BE CAPABLE OF DELIVERING 1,000 GALLONS PER
- MINUTE (GPM) FOR THREE-QUARTERS OF THE CISTERN CAPACITY.

 THE ENTIRE CISTERN AND APPURTENANCES SHALL BE RATED FOR HS-20 HIGHWAY
- LOADING.

 5. DRAWINGS OF THE DESIGN ARE FOR ESTIMATING GENERAL REQUIREMENT AND DESIGN PURPOSES ONLY AND ARE NOT INTENDED FOR USE AS DESIGN.

 6. EACH CISTERN SHALL BE DESIGNED, SITED TO THE PARTICULAR LOCATION, STAMPED BY A REGISTERED ENGINEER, AND APPROVED BY THE FIRE CHIEF.
- BY A REGISTERED ENGINEER, AND APPROVED BY THE FIRE CHIEF.

 ALL SUCTION AND FILE PIPING SHALL BE AMERICAN SOCIETY FOR TESTING MATERIALS

 (ASTM) SCHEDULE 40 STEEL ALL VENT PIPING SHALL BE ASTM SCHEDULE 40 STEEL

 WITH WELDED JOINTS. ALL PIPING LOCATED WITHIN THE TANK SHALL BE ASTM

 SCHEDULE 40 STEEL WITH WELDED JOINTS. ALL PIPING LEADING FROM THE TANK TO

 THE HYDRANT SHALL BE ASTM SCHEDULE 40 STEEL
- THE HYDRANT SHALL BE ASTM SCHEDULE 40 STEEL

 8. THE FINAL SUCTION CONNECTION SHALL BE FIVE INCH PUMPER NOZZLE WITH A CAP.
 THE SUCTION PIPE SHALL BE BRACED TO ENSURE DURABILITY DURING PUMPING
 OPERATIONS. THE FIRE CHIEF SHALL APPROVE BRACE CONFIGURATION AND
 INSTALLATION. THE SUCTION PIPE CONNECTION SHALL BE TWENTY-FOUR INCHES
 ABOVE THE LEVEL OF THE VEHICLE PAD WHERE VEHICLE WHEELS WILL BE LOCATED
- 9. THE FILLER CONNECTION SHALL BE INTALLED INTO THE EIGHT INCH VENT WITH 4' MALE STEEL STORZ FITTING. THIS FITTING SHALL BE 24" ABOVE FINISH GRADE AND FACE THE ROAD, A THIRTY-TWO INCH DIAMETER MANHOLE WITH COVER WILL BE FACE THE ROAD, A THIRTY-TWO INCH DIAMELER MANIFOLE WITH COVER WILL BE LOCATED ON TOP OF THE CISTERN. THE CONFIGURATION OF THIS MANHOLE SHALL ALLOW THE UNIT TO BE SECURED WITH TWO PADLOCKS AND SHALL BE APPROVED BY THE FIRE CHIEF. THE PADLOCKS WILL BE SUPPLIED BY THE FIRE DEPARTMENT. 10. THE DISTANCE FROM THE BOTTOM OF THE SUCTION PIPE TO THE PUMPER CONNECTION SHALL NOT EXCEED FOURTEEN FEET VERTICAL.
- 11. ALL HORIZONTAL SUCTION PIPING SHALL SLOPE SLIGHTLY UPHILL TOWARD THE
- 12. BEDDING FOR THE CISTERN SHALL CONSIST OF A MINIMUM OF TWELVE INCHES OF
- 3/4" TO 1 1/2" WASHED PEA STONE, COMPACTED, NO FILL SHALL BE USED UNDER THE STONE, OVER EXCAVATION SHALL BE FILLED WITH THE SAME STONE BEDDING
- MAIERIAL.

 13. ALL BACKFILL MATERIALS SHALL BE SCREENED GRAVEL WITH NO STONES LARGER
 THAN SIX INCHES AND SHALL BE COMPACTED TO 95 PERCENT OF .1TS ORIGINAL
 VOLUME IN ACCORDANCE WITH ASTM D 1557. 16. THE TOP OF CISTERN SHALL BE
 INSULATED WITH VERMIN RESISTANT FOAM INSULATION AND TWO FEET OF BACKFILL INSULATED WITH VERMIN RESIDENT FORM INSULATION AND THE PET OF BACKFILL WITH A MINIMUM WEIGHT OF 120 PCF, COMPACTED, FOAM USED FOR THIS INSTALLATION SHALL BE CLOSED CELL POLYURETHANE FOAM WITH AN INSULATION FACTOR OR RES PER INCH. ALL BACKFILL SHALL EXTEND THE FEET BEYOND THE EDGE OF THE VEHICLE PAD AND THEN HAVE A MAXIMUM OF 3:1 SLOPE, LOAM AND
- 14. BEFORE ANY BACKFILLING IS DONE THE ENTIRE CISTERN SHALL BE COMPLETED AND INSPECTED BY THE FIRE CHIEF.

 15. AFTER BACKFILLING, BOLLARDS OR LARGE STONES SHALL BE PLACED TO PROTECT
- 15. AFTER BROWNLING, BOULANDS OF CARDE STONES STANLE SE PACED TO PROTECT THE TANK AND APPURTENANCES.

 16. THE PITCH OF THE SHOULDER AND VEHICLE PAD FROM THE EDGE OF THE PACEMENT TO THE PUMPER SUCTION CONNECTION SHALL BE ONE PERCENT TO THREE PERCENT DOWNGRADE.
- 17. THE SHOULDER AND VEHICLE PAD SHALL BE OF A SUFFICIENT LENGTH TO ALLOW CONVENIENT ACCESS TO THE SUCTION CONNECTION WHEN THE PUMPER IS SET AT 45 DEGREES TO THE ROAD. THE SHOULDER AND VEHICLE PAD SECTION SHALL
- CONSIST OF 3" BITUMINOUS PAVING, REFER TO SITE PLAN FOR REQUIREMENTS.

 18. THE SUCTION FITTING SHALL BE LOCATED BETWEEN 22 AND 24 FEET FROM THE NEAREST RUNNING EDGE OF ROAD PAVEMENT. TWO CONCRETE FILLED STEEL BOLLARDS SHALL BE PLACED IN A MANNER TO PROTECT THE HYDRANT. THE BASE
 OF THESE
 BOLLARDS SHALL EXTEND BELOW THE FROST LINE. THE UPPER PORTION OF THE BOLLARDS SHALL EXTEND THIRTY SIX INCHES ABOVE THE LEVEL OF THE VEHICLE PAD WHERE VEHICLE WHEELS WILL BE LOCATED WHEN THE CISTERN IS IN
- 19. ALL CONSTRUCTION, BACKFILL, AND GRADING MATERIALS SHALL BE IN ACCORDANCE WITH PROPER CONSTRUCTION PRACTICES AND SHALL BE ACCEPTABLE TO THE FIRE
- 20. THE FIRE CHIEF (OR REPRESENTATIVE) AND THE ENGINEER'S INSPECTOR WILL BE NOTIFIED BY THE CONTRACTOR TO OBSERVE THE FOLLOWING POINTS OF INSTALLATION:

 A. EXCAVATION COMPLETE.

 - R CRUSHED STONE INSTALLED AND COMPACTED
 - C. BACKFILLING COMPLETE PRIOR TO PLACEMENT OF INSULATION.
 D. PLACEMENT OF INSULATION.
- E. START AND FINISH OF LEAKAGE TEST.
 F. PIPING MANWAYS AND BOLLARDS IN PLACE AND PAINTED.
 G. ALL BACKFILLING LOAM, SEED, ETC. COMPLETE WITH TURNOUT GRAVEL IN
- G. ALL BACKHILLING LOAM, SEED, ETC. COMPLETE WITH LINROUT BRAVEL F
 PLACE AND GRADED.

 H. PAVEMENT COMPLETE, AND ALL OTHER WORK 100% COMPLETE.


 21. THE FIRE CHIEF SHALL BE NOTIFIED OF THE DATE THAT SITE WORK IS TO BEGIN.

 22. ANY EXCEPTION, ADDITIONS, OR DELETIONS ARE DATED AND NOTED BELOW:
- 23 CONCRETE MUST HAVE A MINIMUM OF 150 PCF.
- 24. STONE AND GRAVEL BACKFILL MUST HAVE A MINIMUM OF 120 PCF.

CABERNET BUILDERS P.O. BOX 929 STRATHAM, N.H. 03885


BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863



DEC 23 2013

RECEIVED



TEMPORARY EROSION CONTROL MEASURES

1. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT NO MORE THAN 5 ACRES OF LAND SHALL B

EXPOSED REFORE DISTURBED AREAS ARE STABILIZED*.

EXPOSED BEFORE USIGNABLE ARCAS AREA SHABLIZED.*

2. EROSKON, SEDULENT AND DETERTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED OR DIRECTED BY THE ENGINEER ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS.

3. DISTURBED AREAS SHALL BE LOAMED WITH A KININIUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN 1,10 POUNDS OF SEED PER 1000 SQUARE FEET OF AREA. (48 POUNDS PER ACRE) SEE SEED SPECIFICATIONS THIS SHEET.

SILT SENCES AND OTHER EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND AFTER EVERY RAIN EVENT GREATER THAN D.5"

DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPARCED, SEAMERS AS ASSESSED OF.

5. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VECETATED.

6. AREAS MUST BE SEEDED AND MULCHED WITHIN 3 DAYS OF FINAL GRADING, PERMANENTLY STABILIZED WITHIN 15 DAYS OF FINAL GRADING, OR TEMPORARILY STABILIZED WITHIN 30 DAYS OF INITIAL DISTURBANCE OF SOIL.

* ALL AREA SHALL BE CONSIDERED STABLE IF ONLE OF THE FOLLOWING HAS OFCURRED:

- BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED.

- A MINIMUM OF 58X YECETATED CROWTH HAS BEEN ESTRADISHED.

- A MINIMUM OF 58X TEMPORATED CROWTH HAS BEEN ESTRADISHED.

- EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

CONSTRUCTION SPECIFICATIONS

- STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE APPROPRIATE SPACING.
- 2. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION AND AIR AND
- CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION AND AIR AND WATER POLLUTION WILL BE MINIMIZED. WHEN HAY BALES ARE USED, THE BALES SHALL BE EMBEDDED AT LEAST 4 INCHES INTO THE SOIL. WHEN TIMBER STRUCTURES ARE USED, THE MINER STRUCTURES ARE USED. THE SOIL WHEN THE SOIL USING 2" X 2" STAKES DRIVEN THROUGH THE BALES AND AT LEAST 18 INCHES IN TO THE SOIL.

 SEEDING, FERTILIZING, AND MULCHING SHALL CONFORM TO THE RECOMMENDATIONS IN THE APPROPRIATED

- SEZDING, FERTILIZING, AND MULCHING SHALL CONFORM TO THE RECOMMENDATIONS IN THE APPROPRIATED VEGETATIVE BUP.

 STRUCTURES SHALL BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS BEEN COMPLETED. THROUGHOUT THE DURATION OF CONSTRUCTION ACTIVITES THE CONTRACTOR SHALL TAKE PRECAUTIONS IN CROER TO PREVENT, ABATE AND CONTROL THE EMISSION OF FUGITIVE DUST INCLUDING BUT NOT LIMITED TO WETTING, COVERING, SHELDING, OR VACUUMING.

 THROUGHOUT THE DURATION OF CONSTRUCTION ACTIVITES THE CONTRACTOR SHALL TAKE PRECAUTIONS IN CROER TO PREVENT, ABATE AND CONTROL THE RUSSION OF FUGITIVE DUST INCLUDING BUT NOT LIMITED TO WETTING, COVERING, SHELDING, OR VACUUMING.

 THEN OF COMMISSIONER OF AGRICULTURE PROHIBITS THE COLLECTION, POSSESSION, IMPORTATION, TRANSPORTATION, SALE, PROPAGATION, TRANSPLANTATION, OR CULTIVATION OF PLANTS BANNED BY NH LAW RSA 430:53 AND NH CODE ADMINISTRATIVE RULES ACR 3300. THE PROJECT SHALL MEET ALL REQUIREMENTS AND THE INTENT OF RSA 430:53 AND AGR 3800 RELATIVE TO INVASIVE SPECIES

CONSTRUCTION SEQUENCE

1. CUT AND REMOVE TREES IN CONSTRUCTION AREAS AS REQUIRED OR DIRECTED.

2. CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SEDIMENT EROSION AND DETENTION CONTROL FACILITIES SHALL BE INSTALLED AND STABILIZED PRIOR TO ANY EARTH MOVING OPERATION AND PERMAND CONTROL FACILITIES SHALL BE INSTALLED AND STABILIZED PRIOR TO ANY EARTH MOVING OPERATION AND PRIOR TO DIRECTING RUNOFF TO THEM.

3. CLEAR, CUT, GRUB AND DISPOSE OF DEBRIS IN APPROVED FACILITIES. STUMPS AND DEBRIS ARE TO BE REMOVED FROM STIE AND DISPOSED OF PER STATE AND LOCAL REGULATIONS.

4. EXCAVATE AND STOCKPILE TOPSOIL /LOAM. ALL AREAS SHALL BE STABILIZED IMMEDIATELY AFTER GRADING.

5. CONSTRUCT THE ROADWAY/ORNCEWAYS AND ITS ASSOCIATED DRAINAGE STRUCTURES. ALL ROADWAYS, PARKING AREAS, AND CUT/FILL SLOPES SHALL BE STABILIZED MO/OR LOAMED AND SEEDED WITHIN 72—HOURS OF ACHIEVING

AREAS, AND CUT/FILL SLOPES SHALL BE STABILIZED AND/OR LOAMED AND SEEDED WITHIN 72-HOURS OF ACHIEVING FINISH GRADE AS APPLICABLE.

7. INSTALL PIE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. ALL DISTURBED AREAS

77. INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. ALL DISTURBED AREAS SHALL STRAILZED IMMEDIATELY AFTER GRADING.

8. BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SEEDED OR MULCHED AS REQUIRED, OR DIRECTED.

9. DALLY OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINAGE CHECK DAILY DITCHES, SEDIMENT TRAPS, ETC. TO PREVENT EROSION ON THE SITE AND PREVENT ANY SILATION OF ABUTTING WATERS OR PROPERTY.


10. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION

11. COMPLETE PERMANENT SEEDING AND LANDSCAPING

12. REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE COMPLETE. SMOOTH AND REVEGETARE ALL DISTURBED AREAS.

13. ALL INFLITATION BASINS, GRAVEL WEILANDS, SWALES AND DRAINAGE STRUCTURES SHALL BE CONSTRUCTED AND FULLY STRAILZED (INCLUDING STABLIZATION OF ALL AREAS CONTRIBUTING STORMWATER TO EACH GIVEN STRUCTURE) PRIOR TO HAVING RUNOFF DIRECTED TO THEM.

or to having runoff directed to them. Finish paving All Rodown's/Drirectano on the approved plans shall not commence until the Lot disturbance other than that shown on the approved plans shall not commence until the Dumay has the base course to descin elevation and the associated drainage is complete and stable.



1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 1 TO 2 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.

2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET, EXCEPT FOR A SINGLE RESIDENTIAL LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.

3. THE THICKNESS OF THE ENTRANCE SHALL NOT BE LESS THAN 1 THE FULL WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN 1 THE FULL WIDTH OF THE ENTRANCE SHALL BE PLACED OVER THE ENTRANCE OCCURS OR TO FEET, WHICH EVER IS GREATER. 5. GEOTEXTILE FILLER CLOTH SHALL BE PLACED OVER THE ENTRA REAR PRIOR TO PLACING THE STONE, FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT.

6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL. A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.

7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY. THIS WAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT, ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC RIGHT—OF—WAY MUST BE REMOVED PROMPTLY. THE ANALYSE.

STABILIZED CONSTRUCTION ENTRANCE

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR TO OCTOBER 15TH, SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES OR DETENTION BASINS, SHALL BE LINED WITH BIODEGRADBLE/PHOTODEGRADBLE "JUTE MATTING" (EXCELSIOR'S CURLEX II OR EQUIA.). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE ATTER NOVEMBER 15TH, ANY SNOW THAT ACCUMULTS ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL AREAS WILL BE STABILIZED, AS DIRECTED ABOVE.

2. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPRAP WITH ENCINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED.

3. PRIOR TO NOV. 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS' ELEVATIONS ARE PROPOSED TO REMAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE ROUGHLY CROWNED AND A 3' LAVER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND WILL REDUCE ROADWAY EROSION. THIS CRUSHED CRAVEL DOES NOT HAVE TO CONFORM TO NI DOT 304.3, BUT SHALL HAVE BETWEEN 15-25% PASSING THE #200 SIEVE AND THE LARGEST STONE SIZE SHALL BE Z. IF THE SITE IS ACTIVE AFTER NOVEMBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT WILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH, ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS. FER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT

SEEDING SPECIFICATIONS

WINTER MAINTENANCE

- 1. GRADING AND SHAPING
- A SLOPES SHALL NOT BE STEEPER THAN 2:1;3:1 SLOPES OR FLATTER ARE PREFERRED. WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED.

2. SEEDBED PREPARATION

- A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.
- KILLING OF THE PLANTS.

 B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA WHERE FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO PREPARE A SEEDBED AND MIX FERTILIZER AND LIME INTO THE SOIL THE SEEDBED SHOULD BE LEFT IN REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER PRACTICAL 3. ESTABLISHING A STAND

A LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF SEEDING AND INCORPORATED INTO THE SOIL.
KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST
IS NOT AVAILABLE, THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED.

AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100 LBS PER 1,000 SQ. FT.. NITROGEN(N), 50 LBS PER ACRE OR 1. 1 LBS PER 1,000 SQ.FT.

PHOSPHATE(P205), 100 LBS PER ACRE OR 2. 2 LBS PER 1,000 SQ.FT.

POTASH(K2O), 100 LBS PER ACRE OR 2. 2 LBS PER 1,000 SQ.FT.

(NOTE: THIS IS THE EQUIVALENT OF 500 LBS PER ACRE OF 10-20-20 FERTILIZER OR 1,000 LBS PER ACRE OF 5-10-10.)

B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING. WHERE BROADCASTING IS USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.

REFER TO TABLE(C-E1 THIS SHEET) FOR APPROPRIATE, SEED MIXTURES AND TABLE(H-E1 THIS SHEET) FOR RATES OF SEEDING, ALL LEGUMES (CROWN VETCH, BIRDS FOOT TREFOIL, AND FLAT PEA) MUST BE INOCULATED WITH THEIR SPECIFIC INOCULANT.


D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.

A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEDING.

B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90 LBS PER 1000 SQ. FT.

MAINTENANCE TO ESTABLISH A STAND
A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.

C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.



MAINTENANCE

1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE

IMMEDIATELY.

2. IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.

3. SEDIMENT DEPOSTIS SHOULD BE INSPECTED AFFER EVERY STORM EVENT. THE DEPOSTIS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARDIESE HEIGHT SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARDIESE HEIGHT SHOULD BE REMOVED.

BARRIER. 4. SEDIMENT DEPOSTS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

SEEDING GUIDE

CRAVEL PIT, SEE NH-PN-24 IN APPENDIX FOR RECOMMENDATION REGARDING RECLAMATION OF

1/ refer to seeding mixtures and rates in Table 7–36. 27 Poorly Drained soils are not desirable for use as playing area and athletic fields

DRAINED

G000 G000 G000 FAIR

.GOOD ...

EXCELLENT

SEEDING MIXTURE 1/ DROUGHTY

USE

PILLWAYS, AND HANNELS WITH LOWING WATER

ICKTLY USED PARKIN

EINAMIC

ORAPY GRADE STABILIZATION STRUCTURES SHOULD BE CHECKED AFTER EACH RAINFALL AND AT LEAST DURING PROLONGED STORMS. ANY INCESSARY REPAIRS SHOULD BE MADE MIMEDIATELY. PARTICULAR RISK SHOULD BE GROWN TO BE MADE MIMEDIATELY. PARTICULAR RISK SHOULD BE RECOVED. THE DISTURBED PORTION SHOULD BE RECOVED TO THE STRUCTURE. WHEN STRUCTURES ARE REMOVED, THE DISTURBED PORTION SHOULD BE RECOVED TO THE TRUCTURE WHEN STRUCTURES WHEN THE AREAS PERFARENCES DEED AND MICHED. WHILE THIS PRACTICE IS NOT INTENDED TO BE PRIMARILY FOR SEDIMENT TRAPPING, SOME SEDIMENT MILL ACCUMULATE BERING THE STRUCTURES.

PRIMARILY FOR SEDIMENT TRAPPING, SOME SEDIMENT MILL ACCUMULATE BERING THE STRUCTURES.

PRIMARILY FOR SEDIMENT STRUCTURE. SEDIMENT SHALL BE REMOVED FROM BEHIND THE STRUCTURE.
THE ORIGINAL HEIGHT OF THE STRUCTURE.
REMOVAL.
AFTER VEGETATION HAS STABILIZED, THESE TEMPORARY STRUCTURES SHALL BE REMOVED WITH SPECIAL CARE
AS TO AVOID DISTURBING ANY UNDERLYING EROSION CONTROL FABRIC AND/OR EXISTING VEGETATION

TEMPORARY STONE CHECK DAM

Bare or year HARDWOOD POST SILT FENCE CONSTRUCTION SPECIFICATIONS

SILT FENCE

1. WOVEN WHEE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WHEE TIES OR
STAPLES AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WHEE EVERY 24" AT TOP MID
AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8". 2. THE FENCE

PREPARED FOR-

CABERNET BUILDERS

P.O. BOX 929

STRATHAM, N.H. 03885

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885

PHONE: 603-583-4860, FAX. 603-583-4863

Mix material should consist of 30–50% large (1–3") particles. The organic matter content should be 25%–65%, dry weight basis. The organic matter may originate from a variety of vegetative sources, but needs to be fibrous and elongated. The mix shall be free of silt, clay, fine sand, refuse and contaminants or any material toxic to plant growth. Erosion Control Mix berms are effective filters for overland flow conditions and should not be used to filter concentrated flow such as that found in drainage ditchs, streams, etc.

Erosion Control Mix Berm

AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8". 2. THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A MAXIMUM 10" APART, AND DRIVEN A MINIMUM OF 16" INTO THE GROUND.

3. WHEN TWO SECTIONS OF FILIER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERCAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY-PASSING.

4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERTY DISPOSED OF.

5. PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE FOR SEDIMENT STORAGE.

6. SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER. THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED MIXTURE TALL FESCU CREEPING RED TOP TOTAL 0.45 0.45 0.05 0.85 0.35 0.25 0.35 OR FLAT PEA TOTAL 30 0.75 40 OR 55 0.95 OR 1.35 TALL FESCU FLAT PEA TOTAL 0.45 0.75 1.20 1.15 1.15 2.30 F. TALL FESCUE 1 3,60 1/ FOR HEAVY USE ATHLETIC FIELDS CONSULT THE UNIVERSITY ON NEW HAMPSHIRE COOPERATIVE EXTENSION TURF SPECIALIST FOR CURRENT VARIETIES AND SEEDING RATES.

EROSION & SEDIMENTATION

PLAN FOR: RESIDENTIAL DEVELOPMENT BOULDER DRIVE BARRINGTON, NH

NOTE: TEMPORARY SEED MIX FOR STABILIZATION OF TURF
SHALL BE VINTER RYE OR DATS AT A RATE OF 2.5 LBS. PER
1000 S.F. AND SHALL BE PLACED PRIOR TO OCI, 15. IS FOR PERMANENT SEEDING NOT YET, CONFILETE, I G.F. IS FOR ELLOWING DATE: DEC. 2013 SCALE: NTS PROJ. NO: NH-193 SHEET NO. 12 OF 12

DECEMPE