



TOWN OF BARRINGTON
GOODWILL CONSERVATION
PARKING LOT IMPROVEMENTS
(TAX MAP 233 / LOT 038)
BID PLANS
NOT FOR CONSTRUCTION
BARRINGTON, N.H.

DUBOIS & KING PROJECT NO. 324362P1
MAY 2019



LOCUS MAP
N.T.S.




VICINITY MAP
N.T.S.

DRAWING LIST		
SHEET NUMBER	DRAWING	TITLE
1	C0.0	COVER
2	C1.1	SITE IMPROVEMENTS PLAN & PROFILE
3	C1.2	EROSION CONTROL DETAILS & SECTION VIEWS
4	C1.3	EROSION CONTROL NOTES



18 CONSTITUTION DRIVE, SUITE 8
BEDFORD, NEW HAMPSHIRE 03110
TEL: (603) 637-1043
FAX: (866) 783-7101
www.dubois-king.com















ENGINEERING • PLANNING • MANAGEMENT • DEVELOPMENT
© COPYRIGHT 2019 DUBOIS & KING INC.




NOTES:

1. THE PURPOSE OF THIS PLAN IS TO SHOW THE EXISTING LAND USE AND PROPOSED SITE LAYOUT OF A RECONSTRUCTED GRAVEL PARKING LOT.
2. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REVIEW ALL OF THE DRAWINGS AND SPECIFICATIONS ASSOCIATED WITH THIS PROJECT'S SCOPE OF WORK PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. SHOULD THE CONTRACTOR FIND A CONFLICT WITH THE DOCUMENTS, RELATIVE TO THE SPECIFICATIONS OR APPLICABLE CODES, IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE CONTRACTING OFFICER, IN WRITING, PRIOR TO THE INITIATION OF CONSTRUCTION. FAILURE BY THE CONTRACTOR TO NOTIFY THE CONTRACTING OFFICER SHALL CONSTITUTE ACCEPTANCE OF FULL RESPONSIBILITY BY THE CONTRACTOR TO COMPLETE THE SCOPE OF WORK DEFINED BY THE DRAWINGS AND IN FULL CONFORMANCE WITH LOCAL, STATE, AND FEDERAL CODES AND REGULATIONS.
3. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (O.S.H.A.).
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY NECESSARY PERMITS PRIOR TO CONSTRUCTION. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO BE FAMILIAR WITH THE APPLICABLE PROVISIONS OF EACH PERMIT AS THEY APPLY TO THE WORK AND ABIDE BY THOSE PROVISIONS DURING CONSTRUCTION.
5. SUITABLE EXCAVATED MATERIALS MAY BE INCORPORATED INTO THE PROJECT. UNSUITABLE MATERIAL SHALL BE DISPOSED OF IN ACCORDANCE TO ALL LOCAL, STATE AND FEDERAL LAWS.
6. CONTRACTOR SHALL CLEAR AND GRUB ONLY TO THE LIMITS OF CUT AND FILL.
7. CONTRACTOR SHALL CONSTRUCT TEMPORARY AND PERMANENT EROSION AND SEDIMENTATION CONTROL FACILITIES PRIOR TO THE COMMENCEMENT OF EARTHWORK OPERATIONS. EROSION CONTROL MEASURES SHALL INCLUDE, BUT ARE NOT LIMITED TO, ITEMS IDENTIFIED WITHIN THIS PLAN SET OR WITHIN THE NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES (NHDES) BEST MANAGEMENT PRACTICES (BMP'S) FOR EROSION CONTROL. SEE EROSION CONTROL PLAN AND EROSION CONTROL NOTES & DETAIL SHEET FOR SUPPLEMENTAL INFORMATION.
8. ITEM 304.3 CRUSHED GRAVEL MATERIAL SHALL BE PLACED IN MAXIMUM OF 6" LIFTS. COMPACT EACH LAYER OF EMBANKMENT MATERIAL TO AT LEAST 95% OF MAXIMUM DRY DENSITY (ASTM D1557).
9. ALL AREAS THAT ARE EXCAVATED, FILLED, OR OTHERWISE DISTURBED BY THE CONTRACTOR THAT ARE NOT INTENDED FOR A GRAVEL TOP COURSE SHALL BE LOAMED, GRADED, FERTILIZED, SEEDED, AND MULCHED, UNLESS OTHERWISE NOTED. THE TOP 4 INCHES OF SOIL SHALL BE LOAM.
10. NO GUARANTEE IS MADE OR IMPLIED THAT ACTUAL UTILITIES IN THE PROJECT AREA MATCH WHAT IS SHOWN ON THE PLAN. LOCATION OF PRIVATE UNDERGROUND UTILITIES MAY BE PRESENT. THE CONTRACTOR SHALL BARE ALL RESPONSIBILITY FOR DETERMINING THE PRESENCE AND EXTENT OF ALL UNDERGROUND UTILITIES AND STRUCTURES WITHIN THE PROJECT AREA. THE CONTRACTOR SHALL MAKE ALL INVESTIGATIONS DEEMED NECESSARY TO DETERMINE LOCATION AND EXTENT OF UNDERGROUND UTILITIES. CONTRACTOR SHALL CONTACT DIG-SAFE (811) PRIOR TO START OF ANY EXCAVATION ACTIVITIES. ANY DAMAGE TO ACTIVE UTILITIES SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE OWNER AT NOT ADDITIONAL EXPENSE TO THE OWNER.

LEGEND

<u>EXISTING CONDITIONS</u>		<u>PROPOSED CONDITIONS</u>	
	MINOR CONTOUR		
	MAJOR CONTOUR		LIMIT OF WORK
	EDGE OF WOODS		
	ROADWAY CENTERLINE		EDGE OF WOODS
	EDGE OF ROAD PAVED		MAJOR CONTOUR
	GRAVEL DRIVE		MINOR CONTOUR
	HIKING TRAIL		ROADWAY ALIGNMENT
	WET AREA		EDGE OF GRAVEL
	OVER HEAD POWER LINES		
	WALL STONE		
	EDGE OF POND		AREA TO BE RE-GRADED WITH NEW GRAVEL
	IRON PIPE		
	HVCTRL		PARKING LOT ENTRANCE
	BENCHMARK		
	COMB		
	DECIDUOUS TREE		SILT FENCE



PROFESSIONAL SEAL

BID PLANS

**NOT FOR
CONSTRUCTION**

[illegible]

GOODWILL
CONSERVATION
PARKING LOT
IMPROVEMENTS
245 FRANKLIN
PIERCE HWY
BARRINGTON, NH
03825

DRAWING DESCRIPTION

SITE IMPROVEMENTS PLAN & PROFILE





DRAWN BY BJV	DATE MAY 2019
CHECKED BY JAA	D&K PROJECT # 324362
PROJ. ENG. RLT	D&K ARCHIVE #

DRAWING NO.

C1.1

SHEET 2 OF 4

Figure 1 is a cross-section diagram showing the existing and proposed grades of a road. The horizontal axis represents stationing from -40 to 40, with a centerline at 0+50. The vertical axis represents elevation from 240 to 250. The 'EXISTING GRADE' is shown as a dashed line, and the 'PROPOSED GRADE' is shown as a solid line. The proposed grade is lower than the existing grade in the center and higher at the edges.



1. CONTRACTOR SHALL FOLLOW MANUFACTURER'S INSTALLATION INSTRUCTIONS, ALONG WITH BELOW FENCE-END JOINING INSTALLATION INSTRUCTIONS.
2. FENCE AND ALL COMPONENTS SHALL BE BIODEGRADABLE, AND SHALL BE FUNCTIONAL FOR A MINIMUM OF 1.5 TO 2 YEARS.
3. WHEN TWO SECTION S OF SILT FENCE ADJOIN EACH OTHER AS SHOWN JOINING FENCE SECTIONS.

1. PLACE THE END POST OF ONE FENCE INSIDE THE END POST OF THE OTHER FENCE.
2. ROTATE BOTH POSTS AT LEAST 180 DEGREES IN A CLOCKWISE DIRECTION TO CREATE A TIGHT SEAL WITH THE FABRIC MATERIAL
3. DRIVE BOTH POSTS 18 INCHES INTO THE GROUND AND BURY THE FLAP IN THE TRENCH.

1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAILFALL AND AT LEAST DAILY DURING PROLONGED RAILFALL EVENTS. REPAIRS THAT ARE SHALL BE MADE IMMEDIATELY.
2. IF THE FABRIC OF THE SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.
3. SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY STORM EVENT. THE DEPOSITS SHOULD BE REMOVED WHEN DEPOSITS HAS REACHED APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
4. SEDIMENT DEPOSITS THAT ARE REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

PAVEMENT

RADIUS 15' MIN.

24"x 3"x 6" CRUSHED STONE BERM

STABILIZED SURFACE

24' WIDTH

ROAD SURFACE

3'

50' LENGTH

8" THICK

Detailed description: The drawing consists of two parts. The top part is a plan view showing a rectangular area labeled 'STABILIZED SURFACE' with a width of '24' WIDTH'. To the left of this area is a '24"x 3"x 6" CRUSHED STONE BERM' indicated by a cross-hatch pattern. A curved line with an arrow points to it, labeled 'RADIUS 15' MIN.'. To the left of the berm is a vertical line labeled 'PAVEMENT'. The bottom part is a cross-section view showing the 'ROAD SURFACE' on the left, a '3'' wide shoulder, and a '50' LENGTH' of the stabilized surface. The stabilized surface is shown with a cross-hatch pattern and is labeled '8" THICK'.

1. IN THE EVENT THAT MUD OR SOIL PARTICLES CLOG THE VOIDS OF THE CONSTRUCTION ENTRANCE, THE CONSTRUCTION ENTRANCE SHOULD BE TOPDRESSED WITH NEW STONE. COMPLETE REPLACEMENT OF THE CONSTRUCTION ENTRANCE MAY BE REQUIRED.
2. IF WASH FACILITIES ARE USED, SEDIMENTATION TRAPS SHOULD BE CLEANED AS OFTEN AS NECESSARY TO ASSURE THAT ADEQUATE PERFORMANCE OF SEDIMENTATION COLLECTION AND STORAGE IS AVAILABLE.

1. MANUFACTURER'S INSTALLATION PROCEDURES SUPERSEDE THE FOLLOWING RECOMMENDED PROCEDURES.
2. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP)
3. BEGIN INSTALLATION OF MATTING AT THE TOP OF THE SLOPE BY ANCHORING THE RECP IN A 6" DEEP X 6" WIDE TRENCH WITH 12" (APPROX.) OF RECP EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECP WITH A ROW OF STAPLES/STAKES 12" (APPROX.) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" PORTION OF RECP'S BACK OVER SEED AND COMPACTED SOIL. SECURE RECP OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED 12" (APPROX.) APART ACROSS THE WIDTH OF THE RECP.
4. ROLL THE RECP (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. ALL RECP MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS
5. THE EDGES OF PARALLEL RECP'S SHALL BE STAPLED WITH A 2" TO 5" (APPROX.) OVERLAP.
6. CONSECUTIVE RECP SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH A 3" (APPROX.) OVERLAP. STAPLE THROUGH OVERLAPPED AREA 12" (APPROX.) APART ACROSS ENTIRE RECP WIDTH.
7. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO PROPERLY SECURE THE RECP.

**DuBois
& King inc.**

ENGINEERING • PLANNING •
MANAGEMENT • DEVELOPMENT
18 CONSTITUTION DR. SUITE 8
BEDFORD, NH 03110
TEL: (603) 637-1043
FAX: (866) 783-7101
www.dubois-king.com
LACONIA, NH
RANDOLPH, VT
SOUTH BURLINGTON, VT
SPRINGFIELD, VT
BRANDON, VT

© Copyright 2019 Dubois & King Inc.
PROFESSIONAL SEAL

**NOT FOR
CONSTRUCTION**

[illegible]

GOODWILL
CONSERVATION
PARKING LOT
IMPROVEMENTS
245 FRANKLIN
PIERCE HWY
BARRINGTON, NH
03825

SITE IMPROVEMENTS PLAN & PROFILE

DRAWN BY BJV	DATE MAY 2019
CHECKED BY JAA	D&K PROJECT # 324362
PROJ. ENG. RLT	D&K ARCHIVE #

C1.2

SHEET 3 OF 4

THIS PLAN HAS BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION IN DEVELOPING AREAS AS CONTAINED IN THE NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES (NHDES) STORMWATER MANUAL, VOLUME 3. THE PROPOSED LOCATIONS OF EROSION CONTROL BEST MANAGEMENT PRACTICES (TO BE INSTALLED AT A MINIMUM) ARE SHOWN ON THE PLAN SET HEREIN.

18. AN AREA IS CONSIDERED "STABLE" IF ONE OF THE FOLLOWING HAS OCCURRED: BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED; A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; A MINIMUM OF 3" OF NON-EROSIVE MATERIAL (SUCH AS STONE RIP RAP OR A CERTIFIED COMPOST BLANKET) HAS BEEN INSTALLED; OR EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

SITE PREPARATION:

- 1.1. INSTALL NEEDED EROSION AND SEDIMENT CONTROL MEASURES SUCH AS SILTATION BARRIERS, DIVERSIONS, AND SEDIMENT TRAPS.
- 1.2. GRADE AS NEEDED FOR THE ACCESS OF EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION, AND MULCH ANCHORING.
- 1.3. RUNOFF SHOULD BE DIVERTED FROM THE SEEDD AREA.
- 1.4. ON SLOPES 4:1 OR STEEPER, THE FINAL PREPARATION SHOULD INCLUDE CREATING HORIZONTAL GROOVES PERPENDICULAR TO THE DIRECTION OF THE SLOPE TO CATCH SEED AND REDUCE RUNOFF.

2. SEEDBED PREPARATION:

- 2.1. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH A DISC, SPRING TOOTH HARROW OR OTHER SUITABLE EQUIPMENT. THE FINAL HARROWING OPERATION SHOULD BE ON THE GENERAL CONTOUR. CONTINUE TILLAGE UNTIL A REASONABLY UNIFORM, FINE SEEDBED IS PREPARED, ALL BUT CLAY OR SILTY SOILS AND COARSE SANDS SHOULD BE ROLLED TO FIRM THE SEEDBED WHEREVER FEASIBLE.
- 2.2. REMOVE FROM THE SURFACE ALL STONES 2 INCHES OR LARGER IN ANY DIMENSION. REMOVE ALL OTHER DEBRIS, SUCH AS WIRE, CABLE, TREE ROOTS, CONCRETE, CLODS, LUMPS, TRASH OR OTHER UNSUITABLE MATERIAL.
- 2.3. INSPECT SEEDBED JUST BEFORE SEEDING. IF TRAFFIC HAS LEFT THE SOIL COMPACTED; THE AREA MUST BE TILLED AND FIRMED AS ABOVE.
- 2.4. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF 2 INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED.
- 2.5. IF APPLICABLE, FERTILIZER AND ORGANIC SOIL AMENDMENTS SHOULD BE APPLIED DURING THE GROWING SEASON.
 - 2.5.1. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT FEASIBLE ON SMALL OR VARIABLE SITES, OR WHERE TIMING IS CRITICAL, FERTILIZER MAY BE APPLIED AT THE RATE OF 600 POUNDS PER ACRE OR 13.8 POUNDS PER 1,000 SQUARE FEET OF LOW PHOSPHATE FERTILIZER¹ (N-P2O5-K2O) OR EQUIVALENT. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF 3 TONS PER ACRE (138 LB. PER 1,000 SQUARE FEET).
 - 2.5.2. FERTILIZER SHOULD BE RESTRICTED TO A LOW PHOSPHATE (LESS THAN 2% PHOSPHORUS), SLOW RELEASE NITROGEN (AT LEAST 50% SLOW RELEASE COMPONENT) FERTILIZER WHEN APPLIED TO AREAS BETWEEN 25 FEET AND 250 FEET FROM A SURFACE WATER BODY. NO FERTILIZER EXCEPT LIMESTONE SHOULD BE APPLIED WITHIN 25 FEET OF A SURFACE WATER BODY. THESE LIMITATIONS ARE REQUIREMENTS FOR ANY WATER BODY PROTECTED BY THE COMPREHENSIVE SHORELAND PROTECTION ACT.

3. SEEDING:

- 3.1. INOCULATE ALL LEGUME SEED WITH THE CORRECT TYPE AND AMOUNT OF INOCULANT.
- 3.2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER TYPE SEEDER OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). NORMAL SEEDING DEPTH IS FROM ¼ TO ½ INCH. HYDROSEEDING THAT INCLUDES MULCH MAY BE LEFT ON SOIL SURFACE. SEEDING OPERATIONS SHOULD BE ON THE CONTOUR.
- 3.3. WHERE FEASIBLE, EXCEPT WHERE EITHER A CULTIPACKER TYPE SEEDER OR HYDROSEEDER IS USED, THE SEEDBED SHOULD BE FIRMED FOLLOWING SEEDING OPERATIONS WITH A ROLLER, OR LIGHT DRAG.
- 3.4. SPRING SEEDING USUALLY GIVES THE BEST RESULTS FOR ALL SEED MIXES OR WITH LEGUMES. PERMANENT SEEDING SHOULD BE COMPLETED 45 DAYS PRIOR TO THE FIRST KILLING FROST. WHEN CROWN VETCH IS SEEDD IN LATER SUMMER, AT LEAST 35% OF THE SEED SHOULD BE HARD SEED (UNSCARIFIED). IF SEEDING CANNOT BE DONE WITHIN THE SPECIFIED SEEDING DATES, MULCH ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING PRACTICE," AND DELAY SEEDING UNTIL THE NEXT RECOMMENDED SEEDING PERIOD.
 - 3.4.1. TEMPORARY SEEDING SHOULD TYPICALLY OCCUR PRIOR TO SEPTEMBER 15TH.
 - 3.4.2. AREAS SEEDD BETWEEN MAY 15TH AND AUGUST 15TH SHOULD BE COVERED WITH HAY OR STRAW MULCH, ACCORDING TO THE "TEMPORARY AND PERMANENT MULCHING" PRACTICE PRESENTED IN THE "NEW HAMPSHIRE STORMWATER MANAGEMENT MANUAL VOLUME 3 - CONSTRUCTION PHASE EROSION AND SEDIMENT CONTROLS".
- 3.5. VEGETATED GROWTH COVERING AT LEAST 85% OF THE DISTURBED AREA SHOULD BE ACHIEVED PRIOR TO OCTOBER 15TH. IF THIS CONDITION IS NOT ACHIEVED, IMPLEMENT TEMPORARY STABILIZATION MEASURES FOR OVERWINTER PROTECTION, AND COMPLETE PERMANENT SEED STABILIZATION DURING THE NEXT GROWING SEASON.

4. HYDROSEEDING:

- 4.1. WHEN HYDROSEEDING (HYDRAULIC APPLICATION), PREPARE THE SEEDBED AS SPECIFIED ABOVE OR BY HAND RAKING TO LOOSEN AND SMOOTH THE SOIL AND TO REMOVE SURFACE STONES LARGER THAN 2 INCHES IN DIAMETER.
- 4.2. SLOPES MUST BE NO STEEPER THAN 2 TO 1 (2 FEET HORIZONTALLY TO 1 FOOT VERTICALLY).
- 4.3. LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. THE USE OF FIBER MULCH ON CRITICAL AREAS IS NOT RECOMMENDED (UNLESS IT IS USED TO HOLD STRAW OR HAY). BETTER PROTECTION IS GAINED BY USING STRAW MULCH AND HOLDING IT WITH ADHESIVE MATERIALS OR 500 POUNDS PER ACRE OF WOOD FIBER MULCH.
- 4.4. SEEDING RATES MUST BE INCREASED 10% WHEN HYDROSEEDING.
- 4.5. RECOMMENDED SEEDING:

SPECIES	LBS/ac	LBS/1k S.F.	
TALL FESCUE	20	0.45	
CREeping RED FESCUE	20	0.45	
REDTOP	2	0.05	
	42	0.95	TOTAL

- 5.2. SEEDED AREAS SHOULD BE MOWED AS REQUIRED TO MAINTAIN A HEALTHY STAND OF VEGETATION, WITH MOWING HEIGHT AND FREQUENCY DEPENDENT ON TYPE OF GRASS COVER.

FOR SITE WORK CONSTRUCTION BETWEEN OCTOBER 15TH AND EARLY APRIL THE CONTRACTOR SHALL FOLLOW WINTER CONSTRUCTION EROSION PROTECTION METHODS AS DESCRIBED BELOW:

3. ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

1. STOCKPILES SHALL BE LOCATE A MINIMUM OF 50 FEET AWAY FROM CONCENTRATED FLOWS OF STORMWATER, DRAINAGE COURSES, AND INLETS.
2. STOCKPILES SHALL BE PROTECTED FROM STORMWATER RUN-ON USING TEMPORARY PERIMETER MEASURES SUCH AS DIVERSIONS, BERMS, SANDBAGS, OR OTHER APPROVED PRACTICE.
3. STOCKPILES SHALL BE SURROUNDED BY SEDIMENT BARRIERS TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILES.
4. STOCKPILES SHALL BE PROTECTED FROM WIND EROSION CONTROL PRACTICES AS APPROPRIATE.

**DuBois
King Inc.**