THE CROSSING AT VILLAGE CENTER RESIDENTIAL DEVELOPMENT

NEW HAMPSHIRE FISH AND GAME AOT PERMIT CONDITIONS RELATED TO THREATENED AND ENDANGERED SPECIES

* ALL OBSERVATIONS OF THREATENED OR ENDANGERED SPECIES SHALL BE REPORTED IMMEDIATELY TO THE NEW HAMPSHIRE FISH AND GAME DEPARTMENT NONGAME AND ENDANGERED WILDLIFE ENVIRONMENTAL REVIEW PROGRAM BY PHONE AT 603-271-2461 AND BY EMAIL AT NHFGREVIEW OWILDLIFE. HINGOV. EMAIL SUBJECT LINE: NHB21-0870, PROJECT NAME, WILDLIFE SPECIES OBSERVATION ORDERS SHALL BE PROVIDED FOR VERIFICATION AS FEASIBLE; AND

THE NEW HAMPSHIRE FISH AND GAME DEPARTMENT SHALL HAVE ACCESS TO THE PROPERTY DURING THE TERM OF THE PERMIT.

TERM OF THE PERMIT.

**ALL MANUFACTURED EROSION AND SEDIMENT CONTROL PRODUCTS, UTILIZED FOR, BUT NOT LIMITED TO, SLOPE PROTECTION, RUNOFF DIVERSION, SLOPE INTERRUPTION, PERIMETER CONTROL, AND INLET PROTECTION, CHECK DAMS, SEDIMENT TRAPS, AND SILT FENCE INSTALLED IN ACCORDANCE WITH ENV—WQ 1506.04, SHALL NOT CONTAIN WELDED PLASTIC, PLASTIC, OR MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH.


RECORD OWNERS:

TAX MAP 238 LOT 36 WALDRON HALEY REV LIV TRUST 14 SHAKESPEARE RD. NASHUA, NH 03062

APPLICANT:

J&L TERRA HOLDINGS, INC. 79 EXETER ROAD N. HAMPTON, N.H. 03862









WETLAND/SOIL CONSULTANT:

GOVE ENVIRONMENTAL SERVICES INC. 8 CONTINENTAL DRIVE, BLDG 2 UNIT H EXETER, NH 03833 1-603-778-0644



LOCATION MAP 1"=2000'

REVISED PER PB COMMENTS	11-24-20
REVISED PER ENG. REVIEW	1-7-21
REVISED PER NHDES ANT RMI	7-26-21
E-2	
REVISIONS:	DATE:



REQUIRED PERMITS

NHDES SUBDIVISION APPROVAL NUMBER: SA 2020 NHOES ALTERATION OF TERRIAN NUMBER: NPDES APPROVAL NUMBER:

CIVIL ENGINEERS:

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE. STRATHAM, NEW HAMPSHIRE PHN, 603-583-4860, FAX, 603-583-4863

LAND SURVEYORS:

DAVID W. VINCENT, LLS LAND SURVEYING SERVICES PO BOX 1622 DOVER, NH 03821 1-603-664-5786

RECEIVED

AUG 09 2021


NSTRICT SIY

INDEX

TITLE SHEET	_
SUBDIVISION BOUNDARY PLANS	1-3
EXISTING CONDITION PLANS	4
SITE PLANS	5-6
LIGHTING SITE PLAN	7
HIGHWAY ACCESS PLAN	8
PLAN & PROFILES	9-11
CONSTRUCTION DETAILS	12
UTILITY DETAILS PLAN	13
CISTERN DETAIL PLAN	14
EROSION & SEDIMENT CONTROL DETAILS	15
LANDSCAPE PLANS (BY OTHERS)	


DIAN SET LECEND

	LPWA 201	TEGEND	
OTILITY POLE ORAIN MANHOLE SEWER MANHOLE EXISTING LIGHT POLE EXISTING CATCH BASIN PROPOSED CATCH BASIN EXIST. SPOT GRADE PROP, SPOT GRADE OUBLE POST SIGN SINGLE POST SIGN STREET LIGHT	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	OVERHEAD ELEC. LINE UNDERGROUND ELEC. LINE DRAINAGE LINE SEWER LINE GAS LINE WATER LINE STONE WALL TREE LINE ABUT. PROPERTY LINES EXIST. PROPERTY LINES	
TEST PIT 4000 SF SEPTIC	rxxxxx	BUILDING SETBACK LINES EXIST; CONTOUR	100
RESERVE AREA		PROP. CONTOUR SOIL LINES	
PROP, WELL W/ 75' PROTECTIVE RAD.	\bullet	SILT FENCE OR EROSION CONTROL BERN 30k GAL, FIRE CISTERN	••••



DWG NAME: 014condosite FB: 00


A/30




DWG NAME: 014condosite2 F8 DC

20_014

Sheet 2 of 2



0



Notes:

1.) This plan does not represent a determination of title and the purpose of this plan is to subdivide the subject parcel into two parcels of illiting the boundary information deplicate on the plan reference. Each lot is served by individual septic system and private well.

2.) Pion Error of Cloques Better Thon 1:15,000.

3) Parcet is shown as Lot 38.1 on the Town of Barrington Assessor's Map 238.

Porcet is focated in the Timer Center District, VMage District & Wetland
 Protection District Overlay (50' from edge of jurisdictional wetlands).

) Owner of Record: Woldren & Holley Lining Revocable Trust of 1995 14 Shakespeare Road Nashuc,m NH 03082-2431 SCR0 Re 2048 Pz 242

 a.) Parcel is subject to the terms and restrictions to the State of New Hampshire as described in SCRD 8h 850, Pg 497.

b.) Percel is subject to a Protective Well Radius as described in SCRD 8k 1903, Pg 516.

Porcel has the benefit of on occess ecoement

6.) This plan does not show any unrecorded or unwritten eosements which may said. A reasonable and dispent attempt has been made to observe any opponent, vieible uses of the land; however this does not constitute that no such eosements exist.

7 Percel is not located in a Flood Hezord Zone as depicted on Flood Insurance Rate Map, No. 33017C0305E, Strafford County, NH, (All Aurisolations), Effective Date: May 17, 2005.

8) Existing Lot Area: 29.13 Acres

 The welland areas shown hereon were field delineated by Cove Environmental Services, Inc., of 8 Continental Drive, Building \$2, Unit H, Exeter, NH.

10.) Vertical & Harizontal datum is based upon the plan reference.

EXISTING CONDITIONS PLAN

PREPARED FOR

J & L TERRA HOLDINGS INC.

OF PROPERTY IN THE NAME OF

WALDRON B. HALEY REVOCABLE

LIVING TRUST OF 1998

TAX MAP 238 / LOT 36

CALEF HIGHWAY (NH ROUTE 125) & FRANKLIN PIERCE HIGHWAY (NH ROUTE 9)

COUNTY OF STRAFFORD

BARRINGTON, NH



SCALE: 1"= 100' DATE: SEPTEMBER 3, 2020

DAVID W. VINCENT, LLS

LAND SURVEYING SERVICES

PO BOX 1622


DOVER, NH 03821


TEL/FAX (603) 664-5786

www.landsurveyingservices.net

MAX. LOT COVERAGE

80%





PREPARED FOR

J&L TERRA HOLDINGS, INC. 79 EXETER ROAD N. HAMPTON, N.H. 03862

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863

NOTE

1. UNDOCROPOUND FACILITIES, UTILITIES AND STRUCTURES HAVE BEEN LOCATE PROV FIELD OBSERVANDORS AND THEIR LOCATIONS WIST BE CONSIDERED APPROXIMATE ONLY, BILAIS ASSOCIATES OR ANY OF THEIR EMPLOYTES TAKE NO RESPONSIBILITY FOR THE LOCATION OF ANY UNDERGROUND STRUCTURES OR UTILITIES NOT SHOWN, THAT MAY EXIST, IT IS THE RESPONSIBILITY OF THE CONTRACTION TO HAVE ALL UNDERGROUND UTILITIES OR STRUCTURES LOCATED PRIOR TO EXCAMATION WORK BY CALLING. 1-888-DIG.-584.

- 2. THIS PLAN HAS BEEN PREPARED FOR MUNICIPAL AND STATE APPROVALS. AND FOR CONSTRUCTION ASSED ON DATA OBTAINED ROOM ON-STEE FIELD SURVEY AND EXETING MUNICIPAL RECORDS. THROUGHOUT THE CONSTRUCTION PROCESS, THE CONTRACTOR SHAUL HORSON THE EMPIRED MINEDIATELY OF ANY FIELD DISCREPANCY FROM DATA AS SHOWN ON THE DESIGN PLANS, THIS INCLUDES ANY UNFORESEEN CONDITIONS. SUBSURFACE OR OTHERWISE, FOR EVALUATION AND RECOMMENDATIONS. ANY CONTRACICION OF MEMBER ITEMS OF THIS PLANT/PLAN SET, OR BETWEEN THE 9 CHAIN PLAN SHOW SUST BE RESOLVED BEFORE RELATED CONSTRUCTION MAS SEEN INSTITUTED.
- 3. ALL BENCHWARKS AND TOPOGRAPHY SHOULD BE FIELD VERFIED BY THE CONTRACTOR.
- 4 ALL ROAD AND DRAINAGE WORK TO CONFORM TO TOWN OF BARRINGTON STANDARD SPECIFICATIONS FOR CONSTRUCTION.
- 5. ALL PROPOSED SIGNS SHALL CONFORM TO THE TOWN OF BARRINGTON ZONING REGULATIONS.
- 6 PROJECT IS BASED ON USGS DATUM NAVO 1988. REFERENCE BENCHMARK
- THE DANDOWNER IS RESPONSIBLE TOR COMPLETING WITH ALL APPLICABLE
 LOCAL, STATE AND FEDERAL WETAND REGULATIONS, INCLUDING ANY
 PERMITTING AND SETBACK REQUIREMENTS REQUIRED UNDER THESE
 REGULATIONS
- 8 SEE DETAIL SHEET FOR STANDARD CONSTRUCTION NOTES AND DETAILS.
- 9 DISTURBANCE DVER 100,000 SQ FT. ALTERATION OF TERRIAN PERMIT RSA 485: A-17 REQUIRED.



APPROVAL BLOCK

APPROVED TOWN OF BARRINGTON PLANNING BOARD


CHAIRPERSON

DATE

REVISED PER ENG. REVIEW	1-7-21
ALVISED PER ENG. ALVEN	1 7 21
REVISIONS:	DATE:

SITE PLAN

DATE	AUG. 2020	SCALE:	1"=50"
PROJ_N0:	NH-1263	SHEET NO.	6 OF 15




70/

LOCATION LEGEND BARRINGTON WOOLE SCHOOL

NOTES

- 1. ALL ELECTRICAL, TELEPHONE, CABLE TELEVISION AND ALARM UNES TO BE UNDERGROUND. LOW PROFILE UTILITY BOX STRUCTURES SHALL BE USED TO THE GREATEST EXTENT.
 2. ALL BENCHMARKS AND TOPOGRAPHY SHOULD BE FIELD VERIFIED BY THE CONTRACTOR, ENGINEER TO BE NOTIFIED INVEDIGATELY OF ANY DISCREPANCY.
 3. ALL CONSTRUCTION METHODS AND MATERIALS MILL CONFORM TO THE TOWN OF BARRINGTON STANDARD SPECIFICATIONS AND TO N.H.D.O.T. STANDARDS AND REGULATIONS.



BY-PASS SHOULDER CROSS SECTION

MOTES:
GRAVEL DEPTHS MAY NEED TO BE INCREASED IN AREAS OF POOR SOLLS.
ALL DITCHES TO BE 24' PA DEPTH- (BELOW EDGE OF SHOULDER ELEVATION) GRAVEL MAY BE PLACED AT 12" LIFTS, DENSITY TESTING IS REQUIRED BITUMEN FOR TACK COAT (RS-1) AT 883 GAL/SY

APPLY PAVENENT JOINT ADMESTIVE (TEM 403.16) TO ALL JOINTS


PREPARED FOR:

J&L TERRA HOLDINGS, INC. 79 EXETER ROAD

N. HAMPTON, N.H. 03862

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863




NH9-WB CL TW EP EP TV 11.5' 12' 4.51 3.51

PROFILE SCALES: HORIZONTAL: 1"=50' VERTICAL: 1"=5'


	1	
REVISED PER NHOOT REVIEW	7-2-21	
REVISED PER NHOOT REVIEW	5-3-21	
REVISED PER NHDOT COMMENTS	11-24-20	
REVISIONS:	DATE	

HIGHWAY ACCESS PLAN-H1


DATE	JULY 2020	SCALE 1" = 50']
PROJ. NO:	NH-1263	SHEET NO. 8 OF 15	




SU UTILITY TRUCK ENTERING EASTBOUND DETAIL SCALE: 1"=20"



SU UTILITY TRUCK EXITING WESTBOUND DETAIL SCALE: 1"=20'



SU UTILITY TRUCK ENTERING WESTBOUND DETAIL SCALE: 1"=20"



SU UTILITY TRUCK EXITING-EASTBOUND DETAIL SCALE: 1"=20'

PREPARED FOR:


- J&L TERRA HOLDINGS, INC. 79 EXETER ROAD
- N. HAMPTON, N.H. 03862

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863



WHITE LETTERING





SIGN DETAIL



HIGHWAY ACCESS PLAN-H2


DATE:	DEC: 2020	SCALE:	1"=20"
PROJ. NO:	NH-1263	SHEET NO.	8A OF 15





CONSTRUCTION SPECIFICATIONS FOR STRAW OR HAY BALE BARRIERS

- STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE APPROPRIATE SPACING.
- CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT ERDSION AND AIR AND WATER POLLUTION WILL BE WINNIZED.
- 1. WHEN HAY BALES ARE USED. THE BALES SHALL BE EMBEDDED AT LEAST 4 INCHES INTO THE SOM. WHEN THIBER STRUCTURES ARE USED. THE THIBER SHALL EXTEND AT LEAST 18 INCHES INTO THE SMALL EXTEND AT
- HAY OR STRAW BALES SHALL BE ANCHORED INTO THE SOIL USING 2" X 2" STAKES DRIVEN THROUGH THE BALES AND AT LEAST 18 INCHES INTO THE SOIL.
- 5. SEEDING, FERTILIZING, AND MULCHING SHALL CONFORM TO THE RECOMMENDATIONS IN THE APPROPRIATE VEGETATIVE BMP.
- 5. STRUCTURES SHALL BE REWOVED FROM THE CHANNEL WHEN THEIR USEFUL UFE HAS BEEN COMPLETED.






J&L TERRA HOLDINGS, INC. 79 EXETER ROAD

N. HAMPTON, N.H. 03862

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863



- NOTES


 1. ALL ELECTRICAL, TELEPHONE, CABLE TELEVISION AND ALARM LINES TO BE UNDERGROUND. THE SIZE AND LOCATION IS TO BE DETERMINED BY APPROPRIATE UTILITY COMPANY.

 2. ALL BENCHMARKS AND TOPOGRAPHY SHOULD BE FIELD VERIFIED BY THE CONTRACTOR. ENGINEER TO BE NOTIFIED IMMEDIATELY OF ANY
- CONTRACTOR, ENGINEER TO BE MOTIFIED IMMEDIATELY OF ANY DISCREPANCY.

 3. ALL CONSTRUCTION METHODS AND MATERIALS WILL CONFORM TO THE TOWN STANDARD SPECIFICATIONS AND TO NH.D.T. STANDARDS AND REGULATIONS.

 4. ALL DRAINAGE STRUCTURE AND SWALES WILL BE BUILT AND STABILIZED PRIOR TO HAVING RUN-DFF DIRECTED TO THEM.

 5. SEE DETAIL SHEETS FOR STANDARD CONSTRUCTION NOTES AND DETAILS OF PROPOSED UNDER DRAINS TO BE INSTALLED AS SHOWN ON THE TYPICAL ROAD CROSS SECTION DETAIL AND TIE INTO THE CATCH BASINS.



STONE DRIP EDGE SECTION


PROFILE SCALES: HORIZONTAL 1"=40'

VERTICAL 1"=4"


REVISED PER NHDOT REVIEW	7-2-21
REVISED PER NHDES AUT REVIEW	6-29-21
REVISED PER NHDOT REVIEW	5-3-21
REVISED PER ENG REVIEW	1-7-21
REVISED PER PB COMMENTS	11-24-20


PLAN & PROFILE - P1

DATE:	AUG. 2020	SCALE	1" = 40'
PROJ. NO:	NH-1263	SHEET NO.	9 OF 15



Z4/ /30





MULTI-STAGE DISCHARGE OUTLET CONTROL STRUCTURE

SIDE VIEW

FRONT VIEW

PREPARED FOR:

J&L TERRA HOLDINGS, INC. 79 EXETER ROAD N. HAMPTON, N.H. 03862

BEAUS · ASSOCIATES PILC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863

> SEED ALL SLOPES WITH BLUE SEAL

SCS CONSERVATION MIX AT 2 Ubs./1000 S.F. INLET PROTECTION
SEE DETAIL SHEET
(EXTEND UP 3:1 SLOPE) 6' COARSE SAND LAY FILTER FABRIC BETWEEN SAND AND STONE ELEV. 187.5

6" OF 3/8" WASHED STONE

CROSS SECTION OF INFILTRATION BASIN

INFILTRATION BASIN NOTES

DO NOT TRAFFIC EXPOSED SOIL SURFACE WITH CONSTRUCTION EQUIPMENT. IF FEASIBLE, PERFORM EXCAVATION WITH EQUIPMENT POSITIONED OUTSIDE THE LIMITS OF THE INFILTRATION SYSTEM. AFTER THE INFILTRATION SYSTEM AREA IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR AFTER THE HETLICRATION SYSTEM AREA IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR FOLLOWED BY A PASS WITH A LEVELING DRAG.

DO NOT PLACE INFILTRATION SYSTEM INTO SERVICE UNTIL THE CONTRIBUTING AREAS HAVE BEEN CELLY STABILIZED.

- 1. Protect Infiltration basin area from compaction prior to installation.
 2. After installation, pratect sediment—laden water from entering inlets and pipes.
 3. Install and maintain proper Erosion and Sediment Control Measures during construction.
 4. If necessary, excavate Infiltration basin bottom to an uncompacted subgrade free from rocks and debris. Do NOT compact
- Install Outlet Control Structures.

4' FLEV. 188.5

KEREERY

- 6. Seed and stabilize topsoil. (Vegetate if appropriate with native plantings.)
 7. Do not remove Inlet Protection or other Erosion and Sediment Control measures until site is fully stabilized.
 8. Any sediment that enters inlets during construction is to be removed within 24 hours.

POND STRUCTURE COVER

- Catch Basins and Inlets (upgradient of infiltration basin) should be inspected and cleaned an an annual basis.

 The vegetation along the surface of the Infiltration basin should be maintained in good condition, and any bare spats immediately revegetated.

 Vehicles should not be parked or driven on an Infiltration Basin, and care should be taken to avoid excessive compaction by
- wers.
 Inspect the completed basin and make sure that runoff drains down within 72 hours.
 Also inspect for accumulation of sediment, damage to outlet control structures, erosion control measures, signs of water
- contamination/spills, and slope stability in the berms.

 Mosquito's should not be a problem if the water drains in 72 hours. Mosquitoes require a considerably long breeding period
- Mosquitus static water levels.

 Mow only as appropriate for vegetative cover species.


 Remove sediment from basin accumulations. Restore original cross section and infiltration rate. Properly dispose of sediment.



 	_

BASIN DETAILS

i			
DATE	AUG. 2020	SCALE	1" = NTS
PROJ. NO:	NH-1263	SHEET NO.	10A OF 15




26/30

PROJ. NO:


NH-1263

SHEET NO. 11 OF 15

STONE BERM LEVEL SPREADER



- 1 CONSTRUCT THE LEVEL SPREADER UP ON A OX GRADE TO INSURE UNIFORM SPREADING OF RUNOFF.
- 2 LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL AND NOT ON FILL.
- 3. THE ENTIRE LEVEL LIP AREA SHALL BE PROTECTED BY PLACING EXCELSIOR ENFORCER MATTING BENEATH THE STONE, EACH STRIP SHALL OVERLAP BY AT LEAST SIX INCHES
- 4. THE FLOW FROM THE LEVEL SPREADER SMALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT RE-CONCENTRATE IMMEDIATELY BELOW THE SPREADER.
- 5. MAINTENANCE: THE LEVEL SPREADER SHOULD BE CHECKED PERIODICALLY AND AFTER EVERY MAJOR STORM TO DETERMINE IF THE LIP HAS BEEN DAMAGED AND THE DESIGN CONDITIONS HAVE NOT CHANGED. ANY DETRIMENTAL SEDIMENT ACCUMULATION SHOULD BE REMOVED. IF STONE REMOVAL HAS TAKEN PLACE ON THE LIP, THEN THE DAMAGE SHOULD BE REPAIRED.




NOTE:

1. PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL 1. PAYEMENT REPAIR IN EMISTING RODUMATS SHALL CONFORM TO STREET OPENING REGULATIONS.

2. NEW ROADWAY CONSTRUCTION SHALL CONFORM TO SUBDIVISION SPEC'S.


TYPICAL DRAINAGE TRENCH DETAIL



PART No.	PIPE SIZE	A	B(MAX)	н	L	w
1510-NP	15°	6.5°	10°	5.5°	25°	29°
	375 mm	165 mm	254 mm	165 mm	635 mm	735 mm
1810-NP	18"	7.5°	15"	6.5°	32"	35"
	450 mm	190 mm	380 mm	165 mm	812 mm	890 mm
2410-NP	24"	7.5°	18"	6.5°	36"	45"
	600 mm	190 mm	450 mm	165 mm	900 mm	1140 mm
3010-NP	30" 750 mm	10.5° 266 mm	N/A	7.0° 178 mm	53" 1345 mm	68" 1725 mm
3610-NP	36° 900 mm	10.5" 256 mm	N/A	7.0" 178 mm	53" 1345 mm	68° 1725 mm

PE THREADED ROD W/ WING NUTS PROVIDED FOR END SECTIONS 15"-24", 30" & 36" END SECTIONS TO BE WELDED PER MANUFACTURER'S RECOMMENDATIONS.

ADS N-12 FLARED END SECTIONS NOT TO SCALE (ALL DIMENSIONS ARE NOMINAL)



PIPE OUTLET TO WELL-DEFINED CHANNEL WITH NO DEFINED CHANNEL CONSTRUCTION SPECIFICATIONS

CONSTRUCTION SPECIFICATIONS

1. THE SUB GRADE FOR THE FILTER WATERIAL, GEOTEXTILE FABRIC, AND RIP RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.

2. THE ROCK OR GRAVEL USED FOR FILTER OF RIP RAP SHALL CONFORM TO THE SPECIFIED GRADATION. 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPARED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPILETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPARES OR JOINING TWO PIECES OF FABRIC SHALL BE A MILITURE AND SHALL BE A

MAINTENANCE MAINTENANCE


1 THE OUTLET PROTECTION SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR STORM. IF THE RIP RAP HAS

1 THE OUTLET PROTECTION SHOULD BE CHECKED TO SEE THAT EROSION IS NOT OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF


OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS, AND SEDIMENT THAT COULD CHANGE FLOW PATTERNS AND/OR TAILWATER DEPTHS

ON THE PIPES, REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO OUTLET PROTECTION.

PIPE DUTLET PROTECTION




LWBEE 1-54-1	KECOMMENDED KIL	KHE DKE	DWITTER	KINITULI
THICKNESS OF	RIP RAP = 0.75	FEET	8.5	1.1
d50 SIZE=	0.75	FEET	9	INCHES
% OF WEIGHT THAN THE GIV		SIZE OF	STONE	(INCHES)
100%	and the second	14		18
85%		15		16
50%		9		14
15%		3		5




THE BIT CURBING IS TO BE CONSTRUCTED OF A POLYTIBER CURB MIX CONTAINING 59.2% SANO, 27.6% J/8" STONE, 9.2% 1/2" STONE, 0.3% FIGERS, AND J.0% ASPHALT

CAPE COD BERM DETAIL NOT TO SCALE



NOT TO SCALE




BIT. SIDEWALK DETAIL NOT TO SCALE

DUCTILE IRDN FRAME AND GRATE WITH MSØ LUBBING MEEMEN RW3570A DR EDUAL

PRECAST CATCH BASIN

NOT TO SCALE




PRECAST DRAIN MANHOLE

NOT TO SCALE

SIDEWALK RAMP DETAIL NOT TO SCALE

TYPICAL CROSS SECTION



ALL MATERIALS TO BE INSPECTED AND APPROVED BY TOWN ENGINEER AND MEET NADOT STANDARDS. TOWN MAY REQUIRE UNDERBRAIN OR ADDITIONAL DRAINAGE TO INCLUDE OVER EXCAVATION OF UNSUITABLE MATERIALS AND INSTALLATION OF GEDEEXTILE FABRIC. SEE ADDITIONAL NOTES ON DETAIL SHEETS.

SHEETS.

COMPACTION IS REQUIRED FOR BOTH THE SUBBASE AND BASE MATERIALS. IT SHALL BE PERFORMED BY USING VIBRATING ROLLERS AND WATER IN LIFTS OF NO GREATER THAN TWELVE (12) INCHES.

COMPACTION SHALL BE PERFORMED UNTIL THE REQUIRED DENSITY IS ACHIEVED. BENSITY SHALL BE DETERMINED BY ABSHIOT 1238 METHOD AND SHALL NOT BE LESS THAN 95 PERCENT OF THE MAXIMUM DENSITY DETERMINED IN ACCORDANCE WITH AASHIO IS



PRIME TO BE SET DO NOT THE SES

-ABJUST TO GRADE WITH BRICK OR COME, RINES OF MAXI-


- OPENING + PIPE OA +6

REVISED PER ENG. REVIEW	1-7-21
REVISIONS:	DATE


CONSTRUCTION DETAILS D1


DATE	AUG. 2020	SCALE	NTS'
PROJ. NO:	NH-1263	SHEET NO.	12 OF 15






PLAN








FOR WATER SYSTEM

CROSS-COUNTRY IN PAVEMENT



TYPICAL WATER SERVICE CONNECTION

J&L TERRA HOLDINGS, INC. 79 EXETER ROAD N. HAMPTON, N.H. 03862

BEALS · ASSOCIATES PLLC

70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX: 603-583-4863

NOTES

- DRDERED EXCAVATION OF UNSUITABLE MATURIAL BELOW GRADE: REFILL WITH BEDDING WATERIAL (SEE NOTE 6 ALSO)
- 2) BEDDING MINIMUM 12" SAND BLANKET AS SPECIFIED AND REMAINING | SEDDING - MINIMUM 2" - SAND SLAME I AS SHEEPIED AND PERMINENT FILL AS SCREENED GRAVEL AND/OR CRUSHED STONE FREE FROM CLAY, LOAM, ORCANIC WATERIAL AND MEETING ASTM C-33 STONE SIZE No. 67 | 100% PASSING 1 INCH SCREEN 20-100% PASSING 3/4 INCH SCREEN 20-50% PASSING 3/4 INCH SCREEN 0-10% PASSING 0-10 INCH SCREEN 0-5% PASSING No. 4 SIEVE 0-5% PASSING No. 8 SIEVE

- WHERE ORDERED BY THE ENGINEER TO STABILIZE THE TRENCH
 BASE, GRADED SCREENED GRAVEL OR CRUSHED STONE 3/4 INCH TO
 1-1/2 INCH SHALL BE USED.

 3) SWITABLE MATERIAL IN ROADS, ROAD SHOULDERS, WALKWAYS, AND
 TRAVELED WAYS, SUITABLE MATERIAL FOR TRENCH BACKFILL
 SHALL BE THE NATURAL MATERIAL ECKNAYED DURING THE COURSE
 OF CONSTITUTION, BUS SHALL EXCLUDE DEBTS, PUCKS OF PARKMENT
 ALL EXCLAVED LEDGE MATERIAL, AND ALL ROCKS OVER SIX INCHES
 IN LARGEST DIMENSION.
- FOR CROSS COUNTRY CONSTRUCTION: BACKFILL OR FILL SHALL BE MOUNDED TO A HEIGHT OF 6 INCHES ABOVE THE ORIGINAL GROUND SURFACE.

SEPERATION NOTES:


- WATER MAIN RELATIONS TO SHALL BE IN ACCORDANCE WITH THE "RECOMMENDED STANDARDS FOR WATER WORKS" SO-CALLED TEN STATE STANDARDS AND NEW HAMPSHIRE WATER SUPPLY AND POLLUTION CONTROL DESIGN STANDARDS.
- WATER MAINS SHALL BE LAID AT LEAST 10 FEET HORIZONTALLY FROM ANY EXISTING OR PROPOSED SEWERS. THE DISTANCE SHALL BE MEASURED EDGE TO EDGE. IF THIS DISTANCE CANNOT BE OBTAINED, THEN THE PIPES SHALL BE INSTALLED IN A SEPERATE TRENCH WITH A VERTICAL SPERATION AT LEAST 18 INCHES APART.

THRUST BLOCK DETAILS

PLAN

NOTE: ALL UTILITIES SHALL BE REVIEWED AND APPROVED BY APPROPRIATE UTILITY COMPANY.

SERVICE BOX CONNECTIONS SHALL BE "FLUSH MOUNT" TO GREATEST EXTENT POSSIBLE AND LOCATED AT PROPERTY LINE CORNERS.




UTILITY TRENCH DETAIL



12" MAX.

GAS PIPELINE VATL AND --INSTALLABON BY UTILITY CO.

PLAN




NOTE:


1. PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL
CONFORM TO STREET OPENING REGULATIONS.


2. NEW ROADWAY CONSTRUCTION SHALL CONFORM TO
SUBDIVISION SPEC'S.

TYPICAL SEWER TRENCH DETAIL NOT TO SCALE



SEWER SERVICE CLEAN OUT





REVISED PER ENG. REVIEW DATE: REVISIONS:

UTILITY DETAILS

DATE	AUG. 2020	SCALE	i* = 40'
PROJ. NO:	NH-1203	SHEET NO.	13 OF 15

CISTERN SPECIFICATIONS

- 1, THE CISTERN SHALL BE DESIGNED TO BE TROUBLE FREE, AND IT SHALL BE DESIGNED TO LAST 50
- 2. THE MINIMUM CAPACITY SHALL BE 10,000 GALLONS, DEPENDING ON THE DEVELOPMENT LAYOUT/CONFIGURATION, ADDITIONAL GALLON REQUIREMENTS MAY BE IMPOSED AT THE DISCRETION OF THE FIRE CHIEF. ALL EXCEPTIONS, ADDITIONS, OR DELETIONS WILL BE IN WRITING.
- 3. THE SUCTION CAPACITY SHALL BE CAPABLE OF DELIVERING 1,000 GALLONS PER MINUTE (GPM) FOR THREE-QUATERS OF THE CISTERN CAPACITY.
- 4. THE ENTIRE CISTERN AND APPURTENANCES SHALL BE RATED FOR HS-20 HIGHWAY LOADING.
 5. DRAWINGS OF THE DESIGN ARE FOR ESTIMATING GENERAL REQUIREMENT AND DESIGN PURPOSES ONLY AND ARE NOT INTENDED FOR USE AS DESIGN.
- 6. EACH CISTERN SHALL BE DESIGNED, SITED TO THE PARTICULAR LOCATION, STAMPED BY A REGISTERED ENGINEER, AND APPROVED BY THE FIRE CHIEF.
- REGISTERED ENGINEER, AND APPROVED BY THE THIE. CHIEF.

 7. ALL SUCTION AND FILL PIPMS SHALL BE AMERICAN SOCIETY FOR TESTING MATERIALS (ASTM)

 SCHEDULE 40 STEEL, ALL VENT PIPMS SHALL BE ASTM SCHEDULE 40 STEEL WITH WELDED JOINTS.

 ALL PIPMS LOCATED WITHIN THE TANK SHALL BE ASTM SCHEDULE 40 STEEL WITH WELDED JOINTS.

 ALL PIPMS LEADING FROM THE TANK TO THE HYDRANT SHALL BE ASTM SCHEDULE 40 STEEL.

 8. THE FINAL SUCTION CONNECTION SHALL BE FIVE INCH PUMPER NOZZLE WITH A CAP, THE SUCTION
- PIPE SHALL BE BRACED TO ENSURE DURABILITY DURING PUMPING OPERATIONS. THE FIRE CHIEF SHALL APPROVE BRACE CONFIGURATION AND INSTALLATION THE SUCTION PIPE CONNECTION SHALL BE TWENTY-FOUR INCHES ABOVE THE LEVEL OF THE VEHICLE PAD WHERE VEHICLE WHEELS WILL BE LOCATED WHEN THE CISTERN IS IN USE.
- 9. THE FILLER CONNECTION SHALL BE INTALLED INTO THE EIGHT INCH VENT WITH 4" MALE STEEL STORZ FITTING, THIS FITTING SHALL BE 24" ABOVE FINISH GRADE AND FACE THE ROAD. A THIRTY-TWO INCH DIAMETER MANHOLE MITH COVER WILL BE LOCATED ON TOP OF THE CISTERN. THE CONFIGURATION OF THIS MANHOLE SHALL ALLOW THE UNIT TO BE SECURED WITH TWO PADLOCKS AND SHALL BE APPROVED BY THE FIRE CHIEF. THE PADLOCKS WILL BE SUPPLIED BY THE FIRE DEPARTMENT.
- 10. THE DISTANCE FROM THE BOTTOM OF THE SUCTION PIPE TO THE PUMPER CONNECTION SHALL NOT EXCEED FOURTEEN FEET VERTICAL.
- 11. ALL HORIZONTAL SUCTION PIPING SHALL SLOPE SLIGHTLY UPHILL TOWARD THE PUMPER CONNECTION.
- 12. BEDDING FOR THE CISTERN SHALL CONSIST OF A MINIMUM OF TWELVE INCHES OF 3/4" TO 1 1/2" WASHED PEA STONE, COMPACTED, NO FILL SHALL BE USED UNDER THE STONE, OVER EXCAVATION SHALL BE FILLED WITH THE SAME STONE BEDDING MATERIAL.


 13. ALL BACKFILL MATERIALS SHALL BE SCREENED GRAVEL WITH NO STONES LARGER THAN SIX INCHES
- AND SHALL BE COMPACTED TO 95 PERCENT OF ITS ORIGINAL VOLUME IN ACCORDANCE WITH ASTM 0 1557. 16. THE TOP OF CISTERN SHALL BE INSULATED WITH VERMIN RESISTANT FOAM INSULATION AND TWO FEET OF BACKFILL WITH A MINIMUM WEIGHT OF 120 PCF, COMPACTED, FOAM USED FOR THIS INSTALLATION SHALL BE CLOSED CELL POLYUPETHANE FOAM WITH AN INSULATION FACTOR OF R=5
 PER INCH. ALL BACKFILL SHALL EXTEND TEN FEET BEYOND THE EDGE OF THE VEHICLE PAD AND
- THEN HAVE A MAXIMUM OF 3:1 SLOPE, LOAM AND SEEDED.

 14. BEFORE ANY BACKFILLING IS DONE THE ENTIRE CISTERN SHALL BE COMPLETED AND INSPECTED BY THE FIRE CHIEF.
- AFTER BACKFILLING, BOLLARDS OR LARGE STONES SHALL BE PLACED TO PROTECT. THE TANK AND APPURTENANCES.
- 16. THE PITCH OF THE SHOULDER AND VEHICLE PAD FROM THE FDGE OF THE PAVEMENT TO THE PUMPER SUCTION CONNECTION SHALL BE ONE PERCENT TO THREE PERCENT DOWNGRADE

 17 THE SHOULDER AND VEHICLE PAD SHALL BE OF A SUFFICIENT LENGTH TO ALLOW CONVENIENT
- ACCESS TO THE SUCTION CONNECTION WHEN THE PUMPER IS SET AT 45 DECREES TO THE ROAD. THE SHOULDER AND VEHICLE PAD SECTION SHALL CONSIST OF 3" BITUMINOUS PAYING, REFER TO SITE PLAN FOR REQUIREMENTS.
- 18. THE SUCTION FITTING SHALL BE LOCATED BETWEEN 22 AND 24 FEET FROM THE NEAREST RUNNING FDGE OF ROAD PAVEMENT. TWO CONCRETE FILLED STEEL BOLLARDS. SHALL BE PLACED IN A MANNER TO PROTECT THE HYDRANT THE BASE OF THESE BOLLARDS SHALL EXTEND BELOW THE FROST LINE. THE UPPER PORTION OF THE BOLLARDS SHALL EXTEND THIRTY SIX INCHES ABOVE THE LEVEL OF THE VEHICLE PAD WHERE VEHICLE WHEELS WILL BE LOCATED WHEN THE CISTERN IS IN USE.

 19. ALL CONSTRUCTION, BACKFILL, AND GRADING MATERIALS SHALL BE IN ACCORDANCE WITH PROPER CONSTRUCTION PRACTICES AND SHALL BE ACCEPTABLE TO THE FIRE CHIEF.
- 20. THE FIRE CHIEF (OR REPRESENTATIVE) AND THE ENGINEER'S INSPECTOR WILL BE NOTIFIED BY THE CONTRACTOR TO OBSERVE THE FOLLOWING POINTS OF INSTALLATION:
- A. EXCAVATION COMPLETE.

 B. CRUSHED STONE INSTALLED AND COMPACTED
- C. BACKFILLING COMPLETE PRIOR TO PLACEMENT OF INSULATION
- D. PLACEMENT OF INSULATION. E. START AND FINISH OF LEAKAGE TEST.
- F PIPING MANWAYS AND BOLLARDS IN PLACE AND PAINTED.
 G. ALL BACKFILLING LOAM, SEED, ETC. COMPLETE WITH TURNOUT GRAVEL IN PLACE AND GRADED.
- H. PAVEMENT COMPLETE, AND ALL OTHER WORK 100% COMPLETE.
- 21. THE FIRE CHIEF SHALL BE NOTIFIED OF THE DATE THAT SITE WORK IS TO BEGIN 22. ANY EXCEPTION, ADDITIONS, OR DELETIONS ARE DATED AND NOTED BELOW.
- 23. CONCRETE MUST HAVE A MINIMUM OF 150 PCF.
- 24. STONE AND GRAVEL BACKFILL MUST HAVE A MINIMUM OF 120 PCF.






PREPARED FOR


J&L TERRA HOLDINGS, INC. 79 EXETER ROAD N. HAMPTON, N.H. 03862

BEALS · ASSOCIATES PLLC


70 PORTSMOUTH AVE, STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX: 603-583-4863

TRAFFIC CONTROL SCHEDULE						
SIGN NUMBER	SIGN	SIZE OF		DESCRIPTION	MOUNT TYPE	MOUNT HEIGHT
R1-1	STOP	30"	30"	WHITE ON RED	CHANNEL	7'-0"
R2-1	25	18"	24	BLACK ON WHITE	CHANNEL	7'-0"
41-0342		30"	30"	BLACK ON YELLOW	CHANNEL	8"-6"
W14-2	(VIII)	24"	24"	BLACK ON YELLOW	CHANNEL	7"-0"





PROPOSED 30,000 GAL. FIRE CISTERN DETAIL



STREET SIGN DETAIL 100 x 100 CI-ER) HQEZ PROTZ 100 x 145 CI-SR) HQEZ TERLE DEGRE




56 N	
REVISED PER ENG. REVIEW	1-7-21
REVISIONS:	DATE

FIRE CISTERN DETAILS

DATIE	AUG. 2020	SCALE	NTS
PROJ; No:	NH-1263	SHEET NO.	14 OF 15





TEMPORARY EROSTON CONTROL MEASURES

ILINPURARY ERUSIUN CUNTRUL MEASURES

1. THE SIMILEST PRICTICAL AREA SHALL BE DISTRIBED DURING CONSTRUCTION, BUT NO MORE THAN 5 ACRES OF LAND SHALL BE
DIPOSED BEFORE DISTURBED AREAS ARE SHABUZED.

2. DISSON, SEDMENT AND DETERTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED OR
DIRECTED BY THE CHRINEST ALL DISTURBED AREAS SHALL BE RETURNED TO DRIGHM, CRADES AND ELEVATIONS.

3. DISTURBED AREAS SHALL BE LOANED WITH A MINIMUM OF 4" OF LOMA AND SEDDED WITH NOT LESS THAN 1.10 POUNDS OF SEED
PER 1000 SQUARE FIET OF AREA (48 POUNDS PER ACRE) SEE SEED SPECIFICATIONS THIS SHEET.

4. SALT FENCES AND OTHER PROSON CONTROLS SHALL BE INSPECTED WED'LY AND AFTER EVERY MAIN EVENT GREATER THAN 0.5"
DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPARED, SEDMEDT DEPOSITS SHALL PERIODICALLY BE REMOVED.

DORBIT IN LIFE OF THE PROJECT. AS SEED STABILIZED, THE TEMPORARY CROSION CONTROL MCASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VECTAFED.

AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VECTAFED.

A MEAS MUST BE SEEDED AND MULCHED WITHIN 3 DAYS OF FINAL RETURBANCE OF SOIL.

CRUDING, OR TEMPORARY STABILIZED WITHIN 30 DAYS OF FINAL DISTURBANCE OF SOIL.

A HAREA SHALL BE CONSIDERED STABLE FOR ONE OF THE POLICY WITHIN SO OCCUPRED.

BASE COURSE GRAVELS HAVE BEEN INSTALLED BY AREAS TO BE PAVED.

- ... A AMERICAN OF BSE VEGETATED GROWTH HAS BEEN ESTABLISHED
- A MINIMUM OF 3 MCHES OF MON-BRONE MATERIAL SUCH AS RIPRAP HAS BEEN INSTALLED.
 EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

CONSTRUCTION SPECIFICATIONS.

1. STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE APPROPRIATE SPACING.

APPROPRIATE SPACING.
2. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION AND AIR AND TATER POLLUTION WILL BE MINIMIZED.

WATER POLLUTION WILL BE MINIMIZED.

3. WHEN TIMBER STRUCTURES ARE USED. THE TIMBER SHALL EXTEND AT LEAST 18" INTO THE SOM.

4. STRAW BALES SHALL BE ANCHORED INTO THE SOIL USING 2" X 2" STAKES DRIVEN THROUGH THE BALES AND AT LEAST 18 INCHES IN TO THE SOIL.

5. SEEDING, FERTILIZING, AND MULCHING SHALL CONFORM TO THE RECOMMENDATIONS IN THE APPROPRIATED.

http://cfpubl.epa.gov/npdes/stormwater/noi/noisearch.cfm. AUTHORIZATION IS GRANTED UNDER THE PERMIT ONCE THE NOI IS SHOWN IN "ACTIVE STATUS".

CONSTRUCTION SEQUENCE

I. CUT AND REMOVE TREES IN CONSTRUCTION AREAS AS REQUIRED OR DIRECTED.

2. CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SCOMENT EROSION AND DETENTION CONTROL FACILITIES

2. CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SCOMENT EROSION AND DETENTION CONTROL FACILITIES SHALL BE INSTALLED AND STABILIZED PRIOR

1. CHY CARTH MOVING OPERATION AND PRIOR TO DIRECTING RUNOFF TO THEM. RUNOFF MUST BE DIRECTED TO

AS RECUIRED. EROSION, SEDMENT AND DETERTION CONTROL FACILITIES SMALL BE INSTALLED AND STRUCTURE TO ANY EARTH MAYING OPERATION AND PRIOR TO DIRECTING RUNOFF TO THEM. RUNOFF MUST BE DIRECTED TO TEMPORARY PRACTICES LIMIL STORMMATER BMP'S ARE STABILIZED.

3. CLEAR, CUT, GRUB AND DISPOSED OF DEBR'S IN APPROVED FACILITIES, STUMPS AND DEBRIS ARE TO BE REMOVED FROM SITE AND DISPOSED OF PER STATE AND LOCAL REQULATIONS.

4. EXCANATE AND STOCKPILE TOPSOIL /LOAM. ALL AREAS SHALL BE STABILIZED HIMEDIATELY AFTER GRADING.

5. CONSTRUCT TEMPORARY CULVERTS AS REQUIRED OR DIRECTED.

6. CONSTRUCT TEMPORARY CULVERTS AS REQUIRED OR DIRECTED.

6. CONSTRUCT TEMPORARY CULVERTS AS REQUIRED OR DIRECTED.

7. INSTALL PIPE AND CONSTRUCTION ASSOCIATED AND/OR LOAMED AND SEEDED WITHIN 72-HOURS OF ACHIEVING PINISH GRADE AS APPLICABLE.

7. INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. ALL DISTURBED AREAS SHALL STABILIZED IMMEDIATELY AFTER GRADING.

8. BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS SHALL BE SEEDED OR MULCHED AS REQUIRED, OR DIRECTED.

9. DAILY OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINAGE CHECK DAMS, DITCHES, SEDIMENT TRAPS, ETC.

10. ORDERED AND MAINTAIN ALL EROSION AND SEDIMENT CONSTRUCTION

11. COMPLETE PERMANENT AND ALL SITE AND PREVENT ANY SILTATION OF ABUTTING WATERS OF ROPOPERTY.

10. OMSPECT AND MAINTAIN ALL EROSION AND ASDIDIMENT CONTROL MEASURES DURING CONSTRUCTION


11. COMPLETE PERMANENT SEEDING AND LANDSCAPING

12. REMOVE TEMPORARY ROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE COMPLETE. SMOOTH AND REVEGETATE ALL DISTURBED AREAS.

13. ALL SWALES AND DEMPORANGE STRUCTURES WILL BE CONSTRUCTED AND STABILED PRIOR TO HAVING RUNOFF DIRECTED TO THEM.

14. FINISH PAYING ALL ROADWAYS/DRIVEWAYS.

15. LOT DISTURBBANCE OTHER THAN THAT SHOWN ON THE APPROVED PLANS SHALL NOT COMMENCE UNTIL THE ROADWAY HAS THE BASE COURSE TO DESIGN ELEVATION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABILE.



1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.

2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET, EXCEPT FOR A SINGLE RESIDENTIAL LOT WHEREA A 30 FOOT MINIMUM ENGRIN WOULD APPLY.

3. THE THENCHESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 161 BE LESS THAN 6 INCHES.

4. THE MERCHESS OF CORESS OCCURS OR TO FEET, WHICH EVER IS GREATER. 5. GOTEXTILE FILTER CLOTH SHALL ENGRESS OR EGRESS COCURS OR TO FEET, WHICH EVER IS GREATER. 5. GOTEXTILE FILTER CLOTH SHALL ENGRESS OR EGRESS COCURS OR TO FEET, WHICH EVER IS GREATER. 5. GOTEXTILE FILTER CLOTH SHALL BY PLACED OVER THE ENTRANCE RATA PRIOR TO PLACING THE STONE. FRETER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT.

6. ALL SURFACE WATER THAT IS PLOYMING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PEPED BENEATH THE ENTRANCE. IF PIPMO IS IMPRACTICAL, A BERN WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.

7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RICKING TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEMINATY. ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY.

5. TA DIT IT TO DEMAND.

STABILIZED CONSTRUCTION ENTRANCE

WINTER MAINTENANCE

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR TO OCTOBER 15TH, SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES OR DETENTION BUSINS, SHALL BE LINED WITH BIDDICGRADABLE/PHOTODECRADABLE "JUTE MATTING" (SECELISIOR'S CURIEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SHOW COVER. IF THE SITE IS ACTIVE ATTER NOVEMBERS 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL AREAS WILL BE STABILIZED, AS DIRECTED ABOVE.

2. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MAITED WITH PERMANENT LINERS OR RIPRAP WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED.

3. PRIOR TO OCT, 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS' ELEVATIONS ARE PROPOSED TO RELIAM BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE ROUGHLY CROWNED AND A 3" LAYER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND WILL REDUCE ROADWAY EROSION. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 304.3, BUT SHALL HAVE BETWEEN 13-25% PASSING THE #200 SEVE AND THE JARCEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER NOVEMBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT WILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH, ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT FENCING.

SEEDING SPECIFICATIONS

1. GRADING AND SHAPING

A. SLOPES SHALL NOT BE STEEPER THAN 2:1:3:1 SLOPES OR FLATTER ARE PREFERRED. WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED.

L SURFACE AND SEPACE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PUANTS. 2. SEEDBED PREPARATION

KELLING OF THE MUANTS.

8. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEDING AND FUTURE
MANIFEMANCE OF THE AREA. WHERE FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO PREPARE
A SECORD AND MIX FERTILIZER AND LINE WITO THE SOIL THE SECORDS BOOULD BE LEFT IN REASONABLY FIRM
AND SMOOTH CONDITION. THE LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER PRACTICAL.

3. ESTABLISHING A STAND ESTABLISHING A STAND
A. LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF SEEDING AND INCORPORATED INTO THE SOIL RINDS AND ANOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST IS NOT AVAILABLE, THE FOLLOWING MINIAUM AUDUITS SHOULD BE APPLIED
AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100 LBS PER 1,000 SQ. FT...

HITROGEN(N), 50 LBS PER ACRE OR 1, 1 LBS PER 1,000 SQ.FT. PHOSPHATE(P205), 100 LBS PER ACRE OR 2, 2 LBS PER 1,000 SQ.FT.

POTASH(K20), 100 LBS PER ACRE OR 2, 2 LBS PER 1,000 SQ.FT.

(NOTE: THIS IS THE EQUIVALENT OF 500 LBS PER ACRE OF 10-20-20 FERTILIZER OR 1,000 LBS PER ACRE OF 5-10-10.)

8. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE, METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING, WHERE BROADCASTING IS USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.

C. REFER TO TABLE(G-E1 THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-E1 THIS SHEET)
FOR RATES OF SEEDING. ALL LECUMES (CROWN VETCH, BIRDS FOOT TREFOIL, AND FLAT PEA) MUST BE INOCULATED
WITH THEIR SPECIFIC INOCULANT.

D. WHICH SECTION AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SECTION AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.

4. MULCH

A HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEDING. MULCHING, HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90 UBS PER 1000 SQ FT.

5. MAINTENANCE TO ESTABLISH A STAND

PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH.
FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY
THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO
BECOME ESTABLISHED.

BECOME ESTABLISHED.


IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL MOMING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

MIRE SCREEN SHALL BE PLACED BETWEEN STONE AND BLOCKS TO PREVENT THE ACCRECATE FROM BEING WASHED INTO THE STRUCTURE -CONCRETE BLOCKS - FILITERED WATE LOROP INLET WITH GRATE -- SUBCRADE

MAINTENANCE NOTE: I. ALL STRUCTURES SHOULD BE INSPECTED AFTER EMERY RAINFALL AND REPAIRS MADE AS NECESSARY.

SEDMENT SHOULD BE REMOVED FROM TRAPPING DEVICES AFTER THE SEDMENT HAS REACHED A
MARKING OF ONE HALF THE DEPTH OF THE THAP. THE SEDMENT SHOULD BE DISPOSED BY A
SUITABLE UPLAND AREA AND PROTECTION FROSON BY DITHER STRUCTURE OR VEGETATIVE MEANS.
THE TEMPORARY TRAPS SHOULD BE REMOVED AND THE AREA REPAIRED AS SOON AS THE
CONTRIBUTION DRAINGER EREAL TO THE RELET HAS BEED TO COMPLETELY STABILIZED.

TEMPORARY CATCH BASIN INLET PROTECTION (Block and Gravel Drop Inlet Sediment Filter)



CONSTRUCTION SPECIFICATIONS

1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDOED INTO GROUND A MANDUM OF 8". 2. THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A MAXIMUM 10" APART, AND DRIVEN A

MINIMUM OF 16" INTO THE GROUND.

3. WHICH TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY—PASSING.

BY-PASSING.

4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF.

5. PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE FOR SEDIMENT STORAGE.

6. SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER. THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED

MAINTENANCE


1. SIT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE IMMEDIATELY.

2. IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.


3. SEDMENT DEPOSTS SHOULD BE INSPECTED AFTER EVERY STORM EVENT, THE DEPOSTS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE

BARRIER. 4. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

SEEDING GUIDE



NOTE: TEMPORARY SEED MIX FOR STABILIZATION OF TURF SHALL BE WINTER RYE OR CATS AT A RATE OF 2.5 LBS. PER 1000 S.F. AND SHALL BE PLACED PRIOR TO OCT. 15, IF PERNAMENT SEEDING NOT YET COMPLETE.



Mix material should consist of 30=50% large (1-3") particles. The organic matter content should be 25%-65%, dry weight basis. The organic matter may originate from a variety of vegetative sources, but needs to be fibrous and elongated. The mix shall be free of sit, clay, fine sand, refuse and contaminants or any material taxife to plant growth. Erossion Control Mix berms are effective fâters for overland flow conditions and should not be used to filter concentrated flow such as that found in drainage ditchs, streams, etc.

Erosion Control Mix Berm

SEEDING RATES POUNDS PER POUNDS PER ACRE MOTURE 0.45 0.45 0.05 0.05 TALL FESCUE
CREEPING RED FESCUE
CROWN VETCH
OR
FLAT PEA
TOTAL 0.35 0.25 0.35 40 08 55 0.95 0F 1.35 0.45 0.45 0.20 1.10 TALL FESCUE CREEPING RED FESCUE BIRDS FOOT TREFOIL TOTAL 0.45 0.75 1.20 TALL FESCUE FLAT PEA TOTAL 30 1.15 1.15 2.30 CREEPING RED FESCUE 1/ NEMTUCINY BLUEGRASS 1/ TALL FESCUE 1 150 3.40 1/ FOR HEAVY USE ATHLETIC FIELDS CONSULT THE UNIVERSITY NEW HAMPSHIRE COOPERATIVE EXTENSION TURF SPECIALIST FOR CURRENT WATERIES AND SEEDING NATES.

REVISED PER NINDES ANT RMI	7=26-21
REVISED PER ENG. REVIEW	1-7-21
REVISIONS:	DATE

EROSION & SEDIMENTATION

DATE:	AUG. 2020	SCALE	NTS
PROJ. NO:	NH-1263	SHEET NO.	15 OF 15

