



The State of New Hampshire  
**Department of Environmental Services**

**Robert R. Scott, Commissioner**



---

**WETLANDS AND NON-SITE SPECIFIC PERMIT 2023-00939**

**NOTE CONDITIONS**

**PERMITTEE:** PAUL THIBODEAU  
76 YOUNG RD  
BARRINGTON NH 03825

**PROJECT LOCATION:** ROUTE 9, BARRINGTON  
TAX MAP #234, LOT #77

**WATERBODY:** UNNAMED WETLAND

**APPROVAL DATE:** SEPTEMBER 07, 2023

**EXPIRATION DATE: SEPTEMBER 07, 2028**

---

Based upon review of permit application 2023-00939 in accordance with RSA 482-A and RSA 485-A:17, the New Hampshire Department of Environmental Services (NHDES) hereby issues this Wetlands and Non-Site Specific Permit. To validate this Permit, signatures of the Permittee and the Principal Contractor are required.

**PERMIT DESCRIPTION:**

Dredge and fill 290 SF within palustrine scrub-shrub wetland to install an 18 inch diameter by 32 foot long culvert and construct a 22-foot wide road and associated side slopes to provide access to a proposed multiunit residential development.

**THIS PERMIT IS SUBJECT TO THE FOLLOWING PROJECT-SPECIFIC CONDITIONS:**

1. All work shall be done in accordance with the approved plans dated August 2022 and revised through July 31, 2023, by Beals Associates, PLLC., and received by the NH Department of Environmental Services (NHDES) on August 8, 2023, in accordance with Env-Wt 307.16 and Env-Wt 524.05(b).
2. In accordance with Env-Wt 524.05(a), residential development projects in non-tidal wetlands shall submit a construction notice with the department at least 48 hours prior to commencing work.
3. In accordance with Env-Wt 310.03(a), no other work shall be done on the subject property pursuant to another expedited permit (EXP) for a period of 12 months from the date the EXP was issued unless the property owner submits information, including a plan, to demonstrate that the proposed work is wholly unrelated to and separate from the work already done under the EXP; and the proposed work and the work already done under the EXP do not, when combined, constitute a project for which a standard permit is required.
4. In accordance with Env-Wt 310.03(b), the work shall comply with all applicable conditions specified in Env-Wt 307.
5. No activity shall be conducted in such a way as to cause or contribute to any violation of surface water quality standards per Env-Wt 307.03(a).
6. All work including management of soil stockpiles, shall be conducted so as to minimize erosion, minimize sediment transfer to surface waters or wetlands, and minimize turbidity in surface waters and wetlands per Env-Wt 307.03(b).
7. In accordance with Env-Wt 307.03(c)(3), water quality control measures shall be installed prior to start of work and in accordance with the manufacturer's recommended specifications or, if none, the applicable requirements of Env-Wq 1506 or Env-Wq 1508.

[www.des.nh.gov](http://www.des.nh.gov)

29 Hazen Drive • PO Box 95 • Concord, NH 03302-0095

NHDES Main Line: (603) 271-3503 • Subsurface Fax: (603) 271-6683 • Wetlands Fax: (603) 271-6588

TDD Access: Relay NH 1 (800) 735-2964

8. In accordance with Env-Wt 307.03(c)(1), water quality control measures shall be selected and implemented based on the size and nature of the project and the physical characteristics of the site, including slope, soil type, vegetative cover, and proximity to jurisdictional areas.
9. In accordance with Env-Wt 307.03(c)(2), water quality control measures shall be comprised of wildlife-friendly erosion control materials if erosion control blankets are utilized.
10. In accordance with Env-Wt 307.03(c)(5), water quality control measures shall be maintained so as to ensure continued effectiveness in minimizing erosion and retaining sediment on-site during and after construction.
11. In accordance with Env-Wt 307.03(c)(6), water quality control measures shall remain in place until all disturbed surfaces are stabilized to a condition in which soils on the site will not experience accelerated or unnatural erosion by achieving and maintaining a minimum of 85% vegetative cover using an erosion control seed mix, whether applied in a blanket or otherwise, that is certified by its manufacturer as not containing any invasive species; or placing and maintaining a minimum of 3 inches of non-erosive material such as stone.
12. In accordance with Env-Wt 307.03(c)(7), temporary water quality control methods shall be removed upon completion of work when compliance with Env-Wt 307.03(c)(6) is achieved.
13. In accordance with Env-Wt 307.05(e), to prevent the use of soil or seed stock containing nuisance or invasive species, the contractor responsible for work shall follow Best Management Practices for the Control of Invasive and Noxious Plant Species (Invasive Plant BMPs).
14. In accordance with Env-Wt 307.11(b), limits of fill shall be clearly identified prior to commencement of work and controlled in accordance with Env-Wt 307.03 to ensure that fill does not spill over or erode into any area where filling is not authorized.
15. In accordance with Env-Wt 307.11(a), fill shall be clean sand, gravel, rock, or other material that meets the project's specifications for its use; and does not contain any material that could contaminate surface or groundwater or otherwise adversely affect the ecosystem in which it is used.
16. In accordance with Env-Wt 307.11(e), fill shall be not placed so as to direct flows onto adjacent or down-current property.
17. In accordance with Env-Wt 307.11(d), no fill shall be allowed to achieve setbacks to septic systems specified in Env-Wq 1000.
18. In accordance with Env-Wt 307.12(i), wetland areas where permanent impacts are not authorized shall be restored to their pre-impact conditions and elevation by replacing the removed soil and vegetation in their pre-construction location and elevation such that post-construction soil layering and vegetation schemes are as close as practicable to pre-construction conditions.
19. In accordance with Env-Wt 307.03(e), all exposed soils and other fills shall be permanently stabilized within 3 days following final grading.
20. In accordance with Env-Wt 307.11(c), slopes shall be immediately stabilized by a method specified in Env-Wq 1506 or Env-Wq 1508, as applicable, to prevent erosion into adjacent wetlands or surface waters.
21. In accordance with Env-Wt 307.03(g)(1), the person in charge of construction equipment shall inspect such equipment for leaking fuel, oil, and hydraulic fluid each day prior to entering surface waters or wetlands or operating in an area where such fluids could reach groundwater, surface waters, or wetlands.
22. In accordance with Env-Wt 307.03(g)(3) and (4), the person in charge of construction equipment shall maintain oil spill kits and diesel fuel spill kits, as applicable to the type(s) and amount(s) of oil and diesel fuel used, on site so as to be readily accessible at all times during construction; and train each equipment operator in the use of the spill kits.
23. In accordance with Env-Wt 307.03(g)(2), the person in charge of construction equipment shall repair any leaks prior to using the equipment in an area where such fluids could reach groundwater, surface waters, or wetlands.
24. In accordance with Env-Wt 307.03(h), equipment shall be staged and refueled outside of jurisdictional areas (unless allowed) and in accordance with Env-Wt 307.15.
25. In accordance with Env-Wt 307.15(b), mobile heavy equipment working in wetlands shall not be stored, maintained, or repaired in wetlands, except that repairing or refueling in a wetland is allowed if equipment cannot practicably be removed and secondary containment is provided.

**THIS PERMIT IS SUBJECT TO THE FOLLOWING GENERAL CONDITIONS:**

1. Pursuant to RSA 482-A:12, a copy of this permit shall be posted in a secure manner in a prominent place at the site of the approved project.
2. In accordance with Env-Wt 313.01(a)(5), and as required by RSA 482-A:11, II, work shall not infringe on the property rights or unreasonably affect the value or enjoyment of property of abutting owners.
3. In accordance with Env-Wt 314.01, a standard permit shall be signed by the permittee, and the principal contractor who will build or install the project prior to start of construction, and will not be valid until signed.
4. In accordance with Env-Wt 314.03(a), the permittee shall notify the department in writing at least one week prior to commencing any work under this permit.
5. In accordance with Env-Wt 314.08(a), the permittee shall file a completed notice of completion of work and certificate of compliance with the department within 10 working days of completing the work authorized by this permit.
6. In accordance with Env-Wt 314.06, transfer of this permit to a new owner shall require notification to, and approval of, the NHDES.
7. The permit holder shall ensure that work is done in a way that protects water quality per Env-Wt 307.03; protects fisheries and breeding areas per Env-Wt 307.04; protects against invasive species per Env-Wt 307.05; meets dredging activity conditions in Env-Wt 307.10; and meets filling activity conditions in Env-Wt 307.11.
8. This project has been screened for potential impact to known occurrences of protected species and exemplary natural communities in the immediate area. Since many areas have never been surveyed, or only cursory surveys have been performed, unidentified sensitive species or communities may be present. This permit does not absolve the permittee from due diligence in regard to state, local or federal laws regarding such communities or species. This permit does not authorize in any way the take of threatened or endangered species, as defined by RSA 212-A:2, or of any protected species or exemplary natural communities, as defined in RSA 217-A:3.
9. In accordance with Env-Wt 307.06(a) through (c), no activity shall jeopardize the continued existence of a threatened or endangered species, a species proposed for listing as threatened or endangered, or a designated or proposed critical habitat under the Federal Endangered Species Act, 16 U.S.C. §1531 et seq.; State Endangered Species Conservation Act, RSA 212-A; or New Hampshire Native Plant Protection Act, RSA 217-A.
10. In accordance with Env-Wt 307.02, and in accordance with federal requirements, all work in areas under the jurisdiction of the U.S. Army Corps of Engineers (USACE) shall comply with all conditions of the applicable state general permit.

APPROVED:



Kristin L. Duclos  
Wetlands Specialist, Wetlands Bureau  
Land Resources Management, Water Division

**THE SIGNATURES BELOW ARE REQUIRED TO VALIDATE THIS PERMIT (Env-Wt 314.01).**

---

PERMITTEE SIGNATURE (required)

---

PRINCIPAL CONTRACTOR SIGNATURE (required)